

Lloyd's Register of Shipping. 18 AUG 1941

Ship's Name "PORT CHALMERS" M/V.Official No. 163429.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in CARDIFF - 1940.

At AUCKLAND, N.Z. :- The Tonnage Opening on the Freeboard Deck-(Shelter Deck)- has been
permanently closed by means of 3/8" thick M.S. Plate & 3"X3"X1/2" M.S.
Angles. (E.W. method of attaching plate & Angle to Hatchway). ✓

Wash Ports in way of Tonnage Opening permanently closed. Welded to
Shell Plate. ✓


Overboard Scuppers from Shelter 'Tween Deck closed by means of 5/8"
M.S. welded plates. ✓

All work hose tested and seen tight. ✓

Efficient Drainage arrangements from 'Tween Decks to Bilges provided. ✓


Dated at AUCKLAND, N.Z. this 8th. MAY - 1941.

Signed:-



Surveyor to Lloyd's Register.

A Provisional LOAD LINE CERTIFICATE has been issued dated 8/5/41. valid until 8th. NOV. 1941.

Noted 
19/8/41