

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.—STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey \_\_\_\_\_  
Date of Survey 16-4-32  
Name of Surveyor \_\_\_\_\_

Ship's Name.	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification.
<u>SCYTHIA.</u>					
Number in Register Book _____					

REGISTERED DIMENSIONS FROM	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
Length on DLINE.		Frame Depth Rule	Ceiling Sheer	Peak Tanks
CORRECTED DIMENSIONS.	<u>600.0</u>	<u>72.84</u>	<u>41.80</u>	<u>14258.01</u>

Co-efficient of fineness..... .78  
Any modification necessary }  
[Para. 4 (a) to (e)]\* }  
Co-efficient as corrected ..... .76

Sheer { Stem..... }  
at { Sternpost ... }  $\div 2 =$  ...Mean  
Sheer at  $\frac{1}{2}$  of the length from { Stem }  
{ Sternpost }  $\div 2 =$  ...Mean  
Gradual mean Sheer .....  
Standard mean Sheer [Table, Para. 18] ..... 70.0  
Difference..... 35.0  $\div 4 =$  8.75  
Permitted as Para. 18 (f) 50% EXCESS - 8  $\frac{3}{4}$ "

In Sheer { At front of bridge house..... }  
amidships { 18 (e) } { At after end of forecastle ..... }  
In Sheer { }  
a. 18 (d) }  $\div 2 =$   
h uncovered ..... Correction

ALLOWANCE FOR DECK ERECTIONS :—  
Board, Table C.....  
Correction for Length, if required (Para. 12, 13, and 14) .....  
Board by Table A, corrected for sheer, and for length, }  
if required (Para. 11, 12, 13, and 14) }  
ence .....  
ntage as below.....  
Correction for R. Q. Dk. if engine and boiler openings not }  
covered by bridge house (Para. 11) }  
ance for Deck Erections .....

	Length.	Length allowed.	Height.
Castle.....			
Bridge House .....			
Raised Qr. Dk.....			
Poop.....			
Total .....			
Length of Ship .....			
Corresponding percentage } (Para. 11, 12, 13, or 14) }			

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Steel) Deck :—

Fresh Water Line	above centre of Disc	...	...	...	...	...	...	...	...
Indian Summer Line	" "	...	...	...	...	...	...	...	...
Winter Line	below " "	...	...	...	...	...	...	...	...
Winter North Atlantic Line	" "	...	...	...	...	...	...	...	...

† If frames, skin plating, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.  
† In vessels obtaining an allowance for deck erections under Para. 11 where the sheer drops abaft amidships the height of the R.Q.D. is to be taken from the level of the top of the amidship beam.  
§ In flush-decked vessels the total standard mean sheer means the sheer measured at the stem and stern-post. In vessels having poops and forecastles, it means the sheer measured at points distant one-tenth of the vessel's length from stem and stern-post.

Moulded Depth as measured..... 45'-0"  
WOOD DECK LESS STR. 3  $\frac{1}{2}$ "  
Addition for Keel below base line 44'-8  $\frac{1}{2}$ " TO USE.  
for draught record.....inches.

NOTE.— If the depth is measured when vessel is afloat, the details of measurement should be reported.

CORRECTION FOR LENGTH.  
Length of Ship on Loadline..... 600.00  
Length in Table ..... 536.50  $\times$   
Difference ..... 63.50  $\times$   
Correction for 10ft., Table A. .... 1.7  $\checkmark$  Table C.  
 $\times$  Difference divided by 10 ..... 10.79 (if required.)  
If  $\frac{1}{10}$ ths length covered divide by 2 +10  $\frac{3}{4}$ "

CORRECTION FOR IRON DECK.  
Proportion covered, if less than  $\frac{1}{10}$ ths length covered .....  
Thickness of usual wood deck, less stringer ALLOWED IN MLD. DEPTH.

CORRECTION FOR ROUND OF BEAM.  
Breadth at Gunwale amidships.....  
Round of Beam .....  
Normal round.....  
Difference .....  $\div 2 =$ .....  
Proportion of Deck uncovered (Para. 19) .....

NOTE.— The round of beam should be reported on the full breadth of vessel at the gunwale.

Freeboard, Table A ..... 13'-0  $\frac{3}{4}$ "  $\times$   
Correction for Sheer ..... - 8  $\frac{3}{4}$ "  $\times$   
12'-4"  $\times$   
+ 10  $\frac{3}{4}$ "  $\times$   
13'-2  $\frac{3}{4}$ "  $\times$   
Correction for Length .....  
Allowance for Deck Erections .....  
Correction for Round of Beam.....  $\checkmark$   
Correction for fall in Sheer (if any).....  $\checkmark$   
Correction for Steel Deck (if required) .....  $\checkmark$   
Additions for non-compliance with provisions of {  
Para. 11 (d) and (e) }  
Other Corrections (if any) .....

Winter Freeboard ..... 13'-2  $\frac{3}{4}$ "  $\times$   
Summer Freeboard ..... 8  $\frac{1}{2}$ "  $\times$  12'-6  $\frac{1}{4}$ "  $\times$   
Indian Summer Freeboard .....  
N. A. Winter Freeboard .....  
Correction necessary because clearside amidships, measured }  
in accordance with the Statute is not taken at the }  
intersection of the wood or steel deck with side.

Winter Freeboard from deck line .....  
Summer " " " " .....  
Indian Summer " " " " .....  
N. A. Winter " " " " .....

DEPTH = 45'-0"  
STR = 3  $\frac{1}{2}$ "  
45'-0  $\frac{1}{2}$ "  $\times$   
12'-6  $\frac{1}{4}$ "  $\times$   
32'-6  $\frac{1}{4}$ "

† State dimensions of freeing port area on back of this form.  
† The Surveyor should state whether the fall in sheer as reported is measured relatively to the straight line of keel or to the water line. If measured relatively to water line the vessel's draft at time of survey, and also the usual load draft forward and aft should be reported.

005358-005366-0032

RECEIVED