

REPORT OF SHIP SURVEYS AND REPAIRS

Received London  
5 OCT. 1962

Ship's Name ~~SS/MS~~ "RANA" Gross tons 499.  
 Is there a rpt. 9? yes Port Groningen Rpt. No. 2565a  
 No. of visits 3 First date 17-9-62 Last date 8-10-62  
 Interim Cert. issued & copy herewith? yes Damage rpt. issued & copy herewith? no. Last rpt. (H.Q. only) 19157 lot  
 Date of completing rpt. 11-10-62 Surveyed at, if different from Port above Delfzijl.  
 Surveyed afloat and/or in D.D. slipway Last date of examination in D.D. 27-9-62  
 Has a Load Line survey been held? no. Freeboard Marks verified no.

NOV 1962

9 NOV. 1962

State which additional Rpt. 8 is attached: (Cont); (PS); (DR); (EQ); (Rig)

Survey fees Fl. 40.-- Damage fee Expenses Fl. 9.--

S.A. fee

I have surveyed the above ship in accordance with the Rules for Damage and Condition.

The items now surveyed are detailed on this report. All were found or placed in good condition unless otherwise stated.  
Wear and tear repairs:

Both rudder pintles and bushes welded up with stainless steel, annealed and skimmed up to size.

Found s.s. B5 indented between frames, apparently from grounding but no particulars could be stated. Same however efficient for the present and to be specially examined and dealt with as necessary next special survey.

Specially examined structure under engine (engine removed). Found all in good condition.

S.R.L. Nothing has been done to the temporarily repaired tanktopplating. Notation to be maintained.  
To be noted: Indented bottomshellplate s.s. B5 from forward to be specially examined and dealt with as necessary next special survey.

p.t.o.

I recommend that this ship remain as classed with ~~XXXXX~~ fresh record of dry docking 9-62, subject to tanktopplating of no. 2 D.B. tank s.s. (temporarily repaired 1-62) and indented bottomshellplate s.s. B5 (from forward) being specially examined and dealt with as necessary. *next special survey*

ALSO FOR

SPL FOR

TRO

SRL

POSTING

HEADER

GENU

Where conditions of class are recommended to be retained, imposed, amended or deleted, particulars must be stated above and on the interim certificate.)

Date of Committee

Minute

FRIDAY 30 NOV 1962

*See minute on Casualty file*

A.J. Kraaijenbrink

Surveyor to Lloyd's Register of Shipping

Lloyd's Register Foundation

