

13944  
15th July, 1921.

S.S. "SAN FELIX" -

Rept. No. 74521.

WG

Messrs. Sir W.G. Armstrong Whitworth's 907 ship.  
-----

Positions of auxiliary switchboards and number of switches on each.

- 1 - 5 way auxiliary switchboard fitted outside mess on bridge deck.
- 1 - 3 way section box on dynamo flat.
- 1 - 5 way distribution box on dynamo flat.
- 1 - 8 way distribution box on engine casing port side upper deck.
- 1 - 12 way distribution box on engine casing starboard side upper deck.
- 1 - 2 way section box in engineers workshop.
- 1 - 3 way section box in starboard passage aft upper deck.
- 1 - 12 way distribution box in starboard passage aft ~~upper~~ <sup>SHELTER</sup> deck.
- 1 - 12 way distribution box in port passage aft ~~upper~~ <sup>SHELTER</sup> deck.
- 1 - 12 way distribution box in starboard passage aft shelter deck.
- 1 - 3 way section box in Officers passage bridge deck.
- 1 - 12 way distribution box in Officers passage bridge deck.
- 1 - 12 way distribution box in saloon passage bridge deck.
- 1 - 12 way distribution box in saloon house top passage.
- 1 - 8 way distribution box in charthouse.
- 1 - 10 way distribution box in shelter deck forward.
- 1 - 10 way distribution box ~~in~~ outside after pump room.

Circuits on auxiliary switchboard fitted outside mess on bridge deck.

- D. Officers & Passengers Accommodation -
  - 20 fans
  - 76 lights each of 22-16 CP, 54-20 watt
  - 16-12" fans, 1-16" fan, 3-36" fans
  - requiring total current 34.1 amps.
- E. Navigation & INSTRUMENTS. 19 lights each of 6-8 Cp, 9-16 Cp, 4-32 Cp  
requiring total current 12.0 amps.
- F. Forward pump room 15 lights each of 7-16 cp, 4-20 watt, 4-60 watt  
requiring total current 7.4 amps.
- G. aft pump room 16 lights each of 12-16 cp, 4-60 watt, requiring  
total current 9.6 amps.
- H. Wireless - 25.0 amps.



Branch Cables carrying 88.1 amps comprised of 37 wires each 12 SWG  
dia. .3 square inches.

-do-	-do-	88.1	"	"	"	61	"	"	14
-do-	-do-	34.1	.3029	"	"	7	"	"	16
-do-	-do-	12.0	.0225	"	"	7	"	"	17
-do-	-do-	25.0	.0145	"	"	7	"	"	16
-do-	-do-	7.4	.0225	"	"	7	"	"	17
-do-	-do-	9.6	.0145	"	"	19	"	"	17
			.04						

Surveyor to Lloyd's Register.



© 2020

Lloyd's Register  
Foundation

0324 2/2