

Rpt. &

For the information of Surveyors and the Committee only.

Received at _____ Office _____ 19__

Lloyd's Register of Shipping.

(Report on Vessel No. *496⁵²* Port *Glasgow*.)

The words FORGINGS or CASTINGS, IRON or STEEL, should be struck out as may be required.

No. *2654*. SHIP ~~FORGINGS OR~~ CASTINGS.

I have to report that the undermentioned ~~Iron or Steel Forgings or~~ Castings, manufactured by Messrs *Wm. Beardmore & Co. Ltd.* of *Parkhead, Glasgow*, for the Vessel No. *1223*, ss. *"Armadale"* by Messrs *Wm. Denny & Co. Ltd.* of *Dumbarton*, being built have been inspected by me as set forth below and found to be, so far as can be seen, sound & free from defects.

Castings despatched to the Denny's Iron Works, Dumbarton.

Mark on Forgings or Castings.

Lloyd's
No. _____
R. *Wch.*

William Lewis

2 Rudders Arms Det. 2 Rudders Arms FrG.

	STERN FRAME.	RUDDER FRAME.	STEM.
Material*	<i>Siemens-Martin Acid, Open Hearth Steel</i>		
How made	<i>Cast.</i>		
If annealed	<i>Annealed.</i>		
Dimensions	<i>To pattern</i>		
Progress on Inspection	<i>Rough dressed.</i>		
Date when Inspected	<i>20/11/28 - 28/11/28.</i>	<i>24/11/28 - 28/11/28.</i>	
CASTINGS.			
Tests on Standard Test Pieces.	<i>Test No 781.</i>	<i>Test No 792.</i>	
Tensile Test—			
Tons per square inch	<i>30.4</i>	<i>30.6</i>	
Extension per cent. ...	<i>30.0%</i>	<i>34.0%</i>	
Old Bending Test—			
Angle before fracture	<i>180° W.F.</i>	<i>180° W.F.</i>	
Drop Test—			
Height from ground ...	<i>10 feet</i>	<i>10 feet</i>	
Hammering Test—			
If made according to Rules and found satisfactory ...	<i>Yes.</i>	<i>Yes.</i>	

SKETCHES OF FRAMES SHOWING POSITION AND DESCRIPTION OF WELDS OF FORGINGS.

Fee (if any chargeable) £ *NIL* (Vessel: *Clas*)

To be paid at _____



© 2021

Lloyd's Register
Foundation

If of Iron, state whether scrap or puddled Iron. If of Steel, state whether made on the Open Hearth process.

27. T.

Surveyor

Tested to 2000 lbs. Wm. Denny & Co. Ltd.

J.M.S.