

Lloyd's Register of Shipping.

Ship's Name

" ST MAGNUS "

Official No. 111819

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in July, 1924.

ALTERATIONS: -

The portable steel bridge front bulkhead on frame No. 82 has been removed temporarily and the well space for the accommodation of cattle extended aft to new steel weathertight bulkhead now permanently erected on frame No. 72. (Tonnage bulkheads)

This new bulkhead is of good construction and equivalent in strength to the bulkhead now removed. Provision is made for future opening for passenger purposes when the portable bulkhead is restored to its original position. At present both openings are permanently closed by bolted plates with $\frac{3}{4}$ " bolts spaced 3" apart, centre to centre.

Superstructure length remains unaltered.

Amended tonnages, Gross 1551.21

Underdeck 976.47

Net. 877.92

*William Alcom.*

G.H.W.

194 DEC 1951

