



# Lloyd's Register of Shipping,

LLOYD'S REGISTER, Royal Bank Buildings,  
LONDON. 28, Constitution Street,

REC<sup>d</sup> - 7 FEB 1923 Leith, 6th February, 1923.

ANS<sup>d</sup> 28

Dear Sir,

S.S. "ASIATIC" Leith Report No. 16,237.

In reply to your classing letter of the 30th ultimo, respecting this vessel, I have to state that the thicknesses of the Poop and Forecastle Side plating in way of and clear of the 24" spacing are as given in the report, in consideration of the Poop Side framing in way of the increased spacing being of 9 X 3½ X .50 Bulb angles, and the framing of the Forecastle Side in way of the increased spacing being of 11 X 3½ X .56 Bulb angles.

The butts of the centre strake of tank top plating and the spacing of the rivets through the frames and shell plating are as approved for multiple punching. The spacing of 6 and 5½ diameters given in the report represent the average multiple "dot and dash" spacing in the case of the former figure. The latter figure represents the spacing in way of the Peak Tanks and in bottom plating forward of the 3/5ths. length.

© 2020

Lloyd's Register  
Foundation

005424-005435-04512

(2)

Further to our letter of the 31st ultimo, enquiries have been made here respecting the plans which were forwarded at the same time as the 1st Entry Report, and which according to your letter of the 30th ultimo, have not been received by you, we are informed all parcels posted at that date have gone forward.

We are, Dear Sir,

Yours faithfully,

THE SURVEYORS.

Per.

*Rb.*

The Secretary,  
LONDON.



© 2020

Lloyd's Register  
Foundation

0 05424-005435-0045 2/2

