

Lloyd's Register of Shipping.

Ship's Name "EMPIRE TORRIDGE".

Official No. 147061.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

Alterations in connection with additional accommodation in Bridge Space,
Port side forward.

Strong steel companionway fitted on bridge deck with efficient 2½" wood
door, sill 18" operated on both sides.


Two sidelights on ship's side and one on bridge front fitted with efficient
deadlights.

Sanitary discharge fitted above freeboard deck, with efficient storm valve.

Two goose-neck vents on bridge deck three feet high with plugs and canvas
covers.

One torpedoe vent on bridge front.


Bridge front, port side, tonnage opening closing plate temporarily closed by
welded clips.



SURVEYOR TO LLOYD'S REGISTER OF SHIPPING.

20.11.43.

52.B.
25.11.43



© 2020

Lloyd's Register
Foundation