

Lloyd's Register of Shipping.

Ship's Name Asiatic now "EMPIRE TORRIDGE" Official No. 147061

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in April 1941

The opening & closing appliances in the superstructure bulkheads have now been altered as follows

Poop Bulkhead

one additional hinged steel door now fitted 2' wide 5' high 18" sill

strongly constructed & operated from both sides

Bridge End Bulkhead

(wheel end) 8' 6" high assumed aft.

This bulkhead has been renewed & the portable plate openings S.S.P. have not been re-introduced. One opening with hinged steel door has been re-introduced & one additional hinged steel door 49" wide 46" height sill 29" & one double steel door 49" wide 46" height sill 29" have been fitted. all doors strongly constructed & operated both sides.

The closing appliances as now fitted are as follows

Poop Bulkhead

4 hinged steel doors

Bridge End "

2 openings with hinged steel doors

1 opening with double hinged steel door

One new scupper, one new sink waste pipe & one new soil pipe from new accommodation in Bridge Space S.S. fitted discharging below freeboard deck with brass storm valves at shipside.

One new scupper & one new sink waste pipe from new accommodation in Poop Tween Decks fitted p. & S. & discharging below freeboard deck with brass storm valves at shipside

Boiler
S.B.B.

12 JUL 1943

Clive Bell

W. Hartup

9/7/43



© 2020

Lloyd's Register
Foundation