

Lloyd's Register of Shipping. 24 DEC 1942

Ship's Name ELIZABETE

Official No. 167820.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

Port and starboard side openings at aft end of bridge space now permanently closed with steel plating. A steel companion, strongly constructed, now fitted on bridge deck for entrance to additional accommodation in bridge tween decks. Companion fitted with hinged steel door, operated both sides, having clear opening 4'-6" x 1'-11" with sill 1'-6" above deck. The new accommodation has 3 sidelights in ship's side and one in bridge end all fitted with strongly constructed deadlights. A 2" non-return valve now fitted below upper deck to discharge from additional lavatory accommodation in aft end of bridge space, port side.

J. H. Johnson.
Newcastle-on-Tyne.
18th December 1942.

Copy placed on board vessel & certificate modified in respect of openings in bridge end. J.H.J.

Noted. H.T. 24 DEC 1942 TB.

