

8c.1.31.

FREEBOARD REPORT on the S.S. "Badgestan"

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to :-

- ✓ ① Four air pipes on the freeboard deck 11" high being increased to 36" in height and all air pipes being provided with satisfactory means of closing the openings
- ✓ ② Gangways, lifelines or other satisfactory means being provided for the protection of the crew in the wells
- ✓ ③ The freeing port area in the after well being increased to 23 square feet on each side

The freeboards as computed under the Convention are greater than the existing freeboards therefore the existing freeboards have been re-assigned

APB.
H. H.

12/4/32