

5 MAR 1953

33369

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Mdb. Rpt. No. 1201.

Ship's Name "GLAISDALE".

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Alterations:-

Coal hatch on freeboard deck (P & S) 5'6" x 5'0" plated over after removing coamings. ✓

No.3 hatch on freeboard deck 13'9" x 18'0" plated over after removing coamings. ✓

Coal hatch on bridge deck (P & S) 7'6" x 4'11" plated over after removing coamings. ✓

Companionway of strong steel construction with hinged teak doors operating from both sides fitted on the bridge deck port side in way of plated over coal hatch with a 24" sill. ✓

The following additional air pipes fitted on bridge deck.

3 @ 5" dia. led to oil fuel bunkers height to mouth 23". ✓

2 @ 4" dia. " " settling tanks " " " 23". ✓

2 @ 4" dia. " " No.2 double bottom tank " " 23". ✓

These air pipes fitted with bell mouths, gauges and canvas covers. ✓

Clifford Lee

Surveyor to Lloyd's Register of Shipping, Middlesbrough.

27-2-53.

hc

10 MAR 1953

