

Lloyd's Register of Shipping.

Ship's Name

"GLAISDALE".

Official No.

161012.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The existing hatchway and companion-way on the poop have been dispensed with

A steel deck-house has been constructed on the poop through which access is gained to the poop space. There is one doorway Port and Starboard in the deck house size 4'-8" x 1'-10" height of sill 18" each closed by strongley constructed wood door capable of being operated from both sides.


There are 14 ventilators fitted. 8 on the poop deck and 6 on the deck house each 6" diameter height of coaming 24" all closed by wood plugs and canvas covers.

A steel companion-way entrance to the tunnel escape has been constructed on the poop deck. Doorway 4'-6" x 1'-11" height of sill 18" closed by hinged steel door capable of being operated from both sides.

A new hatchway to storeroom below has been constructed on the poop deck size 2'-0" x 2'-0" height of coaming 30" fitted with wood cover tarpaulins and battening arrangements in accordance with Rule requirements.

The openings in the poop bulkhead have been permanently plated over.

a copy of the above has been placed aboard the vessel.



Noted. 2-JUL 1947