

5m.532.

FREEBOARD REPORT on the "Wulsty Castle"

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval. *subject to*

1. the stiffeners on No 1 Hatch coamings being supported by stays or brackets.
2. The scupper pipes leading to the hold bilges from bridge space being permanently closed by riveted plates; any overboard scuppers in lieu thereof being fitted with storm valves at ship's side.
3. Suitable provision being provided for rigging life lines which shall be available for use in all parts of the vessel which might have to be used by the crew in the regular working thereof.
4. The exposed parts of the machinery casing being additionally stiffened to the Surveyor's satisfaction

Asst Lrs 6/9/26

Convention  
2 Plans to be returned



© 202

*Handwritten:* H.W. 5/8/36

Lloyd's Register  
Foundation

005926-005839-0348