

June 4. 1917

# REPORT of SURVEY for REPAIRS, &c.

Writing Report 1st June 1917 When handed in at Local Office 1st June 1917 Port of DETROIT, MICH.

Survey held at Toledo, Ohio. Date, First Survey 25th April Last Survey 10th May 1917

On the ~~Wood, Iron or Steel~~ S.S. "HORACE S. WILKINSON" Master R. J. Lyons

Tonnage:— 8338 Built at Toledo, Ohio. By whom Toledo S. B. Co. When 1917 MONTH 5

Owners Great Lakes Steamship Co. Port belonging to Oswego.

Owners' Address 6879 (If not already recorded in Appendix to Register Book).

Keel Afloat or in Dry Dock? Dry Dock Name of Dock Toledo S. B. Co. Destined Voyage Great Lakes

Cell/D/Bor/D/Ba feet; u/E&B feet; f feet; l capacity tons. FPT tons; APT tons; MT feet tons.

Particulars of Classification (which must be inserted precisely as in Register Book & Supplements).

st Report, No. Port

Medical Surveys, when held, must be reported in detail and seriatim in the terms of the Rules. State clearly the nature of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent repairs. Repairs account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; besides being detailed in the body of the report, should be summarised in the form shown below. Whenever the placement of Anchors or Chains is reported, the particulars should be clearly stated in the space provided on back of this form. State also the dates and initials of any letters respecting this case.

Damage cases where the Surveyor has not made a special damage report he is required to state whether he offered his services for this purpose and why they were declined? Yes, not required. Was a damage report made by anyone else? If so, by whom? Mr C. Lincoln.

Repairs, OR EXAMINATION AS PER RULE, FOR Damage stated to have been caused by striking the dock wall when launching on the 21st April 1917.

How done:— Vessel placed in dry dock and bottom examined.

Starboard Side:— D2, E1, 8, 9, 12, 16, 17 & 18 removed, faired & replaced.

E7, 15, 17 & 19 faired in place. 3 Bilge frames & lower part of 2 web frames renewed. 24 Bilge frames & 14 bilge brackets removed, faired & replaced. 1 Web frame & 7 bilge brackets faired in place.

Port Side:— D20 removed, faired & replaced. C21 faired in place.

Fee (per Section 95)	2	Fees applied for,
Damage or Repair Fee (if any)	2	19
Expenses (if chargeable)	2	Received by me,
Surveyor's Fee (if any)	2	19

Committee's Minute New York JUN 5 1917

Character Assigned See Detroit Rpt No 43

E. J. Evans  
Surveyor to Lloyd's Register of Shipping.



006028-006038-0227