

COPY

DISCLOSED
ACTION

862.

11th October, 1947.

XXXXXXXXXXXXXXXXXX
XXXXXXXXXXXXX
XXXXXXXXXXXXX

Dear Costantini,

"ARAYBANK"

Thanks for your letter of the 6th October.

The original freeboards (18.10.40) from
steel shelter deck were:-

Summer	11'-11 $\frac{1}{2}$ "
Tropical fresh		10'-9 $\frac{3}{4}$ "
Fresh Water		11'-4 $\frac{1}{2}$ "
Tropical		11'-4 $\frac{1}{2}$ "
Winter		12'-6 $\frac{1}{2}$ "

This corresponds with the draught for
a C.S.S. ship having a virtual moulded depth of 30.58
feet to the second deck (i.e. 8 feet below shelter
deck). The actual moulded depth to the second deck
was 29'-10".

The vessel never had wartime deeper
loading either under Memorandum M.3387/41 or
Memorandum M.151969/41, being sunk in either 1940 or
early 1941.

Yours ever,

M. COSTANTINI, ESQ.,
GENOA.



© 2020

Lloyd's Register
Foundation

006512-006522-0066