

Messrs. Harland & Wolff's Nos. 1034-5

Owners:- Andrew War & Co.

Dimensions:- 425 x 57 x 29.83 and 38.58

These vessels which are duplicates of the "NEBANK" built in 1937, are being built with large openings, and the Builders desire to be informed if any increase in draught can be given if tonnage opening is closed.

The scantlings have been compared with the requirements of the Rules for a C.S.S. vessel having a value of D of 38.58, and it is found that:-

Framing:- Equivalent to C.S.S.

Shell:- do.

Strength Dk:- do.

It is submitted the scantlings are such as to entitle the vessel to a draught corresponding to a C.S.S. ship having a depth of 38.58 to the C.S.S. and a normal height of tween decks.

It is noted the Owners propose to extend the knees to the weather deck.

19th February, 1940.



© 2020

Lloyd's Register
Foundation

006512-006522-0100