

30610

Lloyd's Register of Shipping.

Ship's Name *S.S. "EGYPTIAN PRINCE"*Official No. *146667*

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

New accommodation for ten gunners has been fitted in the Shelter 'tween decks port side in and forward of the tonnage space. Entrance to new accommodation is by a new companionway strongly constructed of welded steel plates suitably stiffened with angle bars and welded on top of steel closing plate on tonnage hatchway, opening to suit cut in closing plate. Opening for door cut on the inboard side of companionway 4'-6" x 2'-1" having coaming 20" high above top of tonnage hatchway and fitted with a hinging wood door capable of being operated from both sides. Two 8" dia. cowd ventilators having coamings 30" high by 5/16" thick and one 4" dia. gooseneck fitted, ventilators welded to deck and supplied with wood plugs and canvas covers. Three 12" dia. and one 16" dia. cast brass side scuttles having cast iron deadlights fitted on the shell plating port side in way of new accommodation. Two new waterclosets and two new washbasins fitted discharging overboard through one 4" dia. self closing automatic storm valve fitted on the shell plating below the main deck. Storm valve controlled from above the Shelter deck.

A copy of this report will be forwarded to the Owner's for attachment to Freeboard report.

Alex. M. Jenkins
Surveyor to Lloyd's Register of Shipping
LONDON.

21ST SEPTEMBER 1943.

Noted.
E. J. B.