

# Lloyd's Register of Shipping.

Ship's Name "EGYPTIAN PRINCE"

Official No. 146667

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in \_\_\_\_\_

Tonnage opening hatch closed by steel plate, with beams under welded permanently in place except for hatch 54" x 40" x 32" high which is fitted with wood covers, cleats, battens, wedges and tarpaulins.

Tonnage opening, freeing ports permanently closed by welded spigot patches.


Uncontrolled scuppers and sanitary discharge pipes from spaces below shelter deck permanently closed by welded spigot patches.

All drains from tween deck spaces led to bilges.

Fittings for life lines installed on shelter deck.

Vessel found in satisfactory condition and closing appliances for deck openings in good order.

May 2, 1941

  
Surveyor to Lloyd's Register of Shipping

