



(LLOYD'S REGISTER.)

G.R. 130.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Signal Letters (if any) K.N.C.M.

Official Number.	Name of Ship.		No., Date, and Port of Registry.	
146,667.	Egyptian Prince		274 in 1922 LONDON.	
No., Date, and Port of Previous Registry (if any) -----				
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw	Haverton Hill-on-Tees.	1922.	Furness Shipbuilding Co., Ltd., Haverton-Hill-on-Tees.
Number of Decks	Single & Shelter	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post		Feet. 363 Tenths. 3
Number of Masts	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel		362 7.5
Rigged	Fore & Aft.	Main breadth to outside of plank		52 2.5
Stern	Conical cruiser	Depth in hold from tonnage deck to ceiling at midships		22 --
Build	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards		25 8.3
Galleries	Nil	Depth from top of beam amidships to top of keel		24 9.8
Head	Nil	Depth from top of deck at side amidships to bottom of keel		1 0.8
Framework and description of vessel	Steel Cargo	Round of beam		1 0.8
Number of Bulkheads	7 W.T. 1 Non W.T.	Length of engine room, if any		49 4
Number of water ballast tanks and their capacity in tons	1 Deep - 645 Tons			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel } 7314 Tons. Ditto per inch immersion at same depth } 35.53 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B.H.P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Inverted Direct Acting Triple Expansion condensing	Engines. British	Engines. 1922	Engines. Richardsons, Westgarth & Co. Ld.,	Three 26" 43" 73"	48"		359 --- 2750
One	S.E. Cylindrical multitubular	Boilers. British	Boilers. 1922	Hartlepool.				11 1/2 Knots

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	2911.14	On account of space required for propelling power	1340.12
Space or spaces between Decks, House in Shelter Deck	57.42	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Turret or Trunk House in Forecastle	13.76	These spaces are the following, viz.:-	
Forecastle	7.18	Round Houses, Poop.	282.21
Bridge space			
Poop or Break	95.73		
Side Houses			
Deck Houses	244.59		
Chart House	6.12		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	154.38	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows: -	
Excess of Hatchways		Masters Accommodation	15.09
		Boatswains Store	13.23
		Chart Space	6.12
		Wireless Telegraphy Space	4.99
		Water Ballast (Fore Peak)	12.30
		Water Ballast (After Peak)	12.53
Gross Tonnage	3490.32	Total	1686.59
Deductions, as per Contra	1686.59		
Registered Tonnage	1803.73		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 611.40 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 159.94 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Forecastle L. 67ft	- 155.82 Tons	Passageways in way of machinery casings on Shelter Deck L. 46.8)	26.79 Tons
Shelter Deck Space I L. 307.3 ft.	- 997.57 Tons	Open space under	40.7)
end of boat deck L. 1.9 ft	- 3.43 Tons.		
Shelter Deck Space II L. 4.1 ft	: 13.89 Tons		

Name of Master	Certificate of Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	Norman Stockdale of same address.
Prince Line Limited, 56 Leadenhall Street, Sixty-four Shares.	Manager.

Dated 4th November 1922.

