

# REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL) **RECEIVED** FEB. 15 1922  
Received at London Office

Date of writing Report 10 When handed in at Local Office 22. 11. 1922 Port of Middlesbrough

No. in Survey held at Haverton Hill-on-Tees Date, First Survey 21. 3. 21 Last Survey 25. 10. 1922  
Reg. Book. 79882 on the Steel Screw Steamer "Egyptian Prince" (Number of Visits 13)

Tons { Gross 3496  
Net 1800

Built at Haverton Hill / Tees By whom built Furness S/B Co Ltd Yard No. 27 When built 1922

Owners Prince Line Ltd Port belonging to London

Electric Light Installation fitted by Furness Shipbuilding Co Ltd Contract No. ✓ When fitted 1922

System of Distribution Double Wire

Pressure of supply for Lighting 100 volts, Heating - volts, Power 100 volts.

Direct or Alternating Current, Lighting D.C Power D.C

If alternating current system, state frequency of periods per second -

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off yes ✓

Generators, do they comply with the requirements regarding overload yes ✓, are they compound wound yes ✓

are they over compounded 5 per cent. Level, if not compound wound state distance between each generator -

Where more than one generator is fitted are they arranged to run in parallel No, is an adjustable regulating resistance fitted in series with each shunt field yes ✓

Are all terminals accessible and clearly marked yes ✓, are they so spaced or shielded that they cannot be accidentally earthed, or short circuited yes ✓ Are the lubricating arrangements of the generators as per Rule yes ✓

Position of Generators (Freshwater) Tank room - port side Tween Decks

is the ventilation in way of the generators satisfactory yes ✓, are they clear of all inflammable material yes ✓

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators - and -, are the generators protected from mechanical injury and damage from water, steam or oil yes ✓

are their axis of rotation fore and aft yes ✓

Earthing, are the bedplates and frames of the generating plant efficiently earthed yes ✓ are the prime movers and their respective generators in metallic contact yes ✓

Main Switch Boards, where placed Near Generators in Tank Room Port Side Tween Dks

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard -

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes yes ✓

are they protected from mechanical injury and damage from water, steam or oil yes ✓, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards - and -

are they constructed wholly of durable, incombustible non-absorbent materials yes ✓, is all insulation of high dielectric strength and of permanently high insulation resistance yes ✓, if semi-insulating material is used, are all conducting parts connected to one pole

insulated from the slab with mica or micanite and the slab similarly insulated from its framework yes ✓, and is the frame effectively earthed yes ✓ Are the following fittings as per Rule, viz. :- spacing or shielding of live parts

yes ✓, accessibility of all parts yes ✓, absence of fuses on back of board yes ✓, proportion of omnibus bars yes ✓, individual fuses to voltmeter, pilot or earth lamp yes ✓, connections of switches yes ✓

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches


D.P. Switch & fuse for each generator & Outgoing circuit & D.P. Change Over Switch for connecting Generator alternatively to Bus Bars (Fuses Porcelain H.O. pattern)

Instruments on main switchboard 2 ammeters 1 voltmeters - synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system Two 16 c.p. lamps in series & middle point earthed. Connected to each Bus Bar by means of Switch & fuse

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules yes ✓

Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule yes ✓



**Insulation of Cables**, state type of cables, single or twin Single Twinn are the cables insulated and protected as per Tables III or IV of the Rules Table III

**Fall of Pressure**, state maximum between bus bars and any point of the installation under maximum load 5 volts

**Cable Sockets and other connections**, are the ends of all cables having a sectional area of 0.007 square inch and above provided with soldering sockets yes

**Paper Insulated Cables**. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound

**Cable Runs**, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage Main feeder cables are run on weather deck

**Support and Protection of Cables**, state how the cables are supported and protected lead covered and armoured cables are supported by means of Galvanized iron clips & screws lead covered cables being supported by brass clips & screws

If cables are run in wood casings, are the casings and caps secured by screws —, are the cap screws of brass —, are the cables run in separate grooves —. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VI yes

**Refrigerated Chambers**, if lights are fitted, are the cables and fittings in accordance with the special requirements —

**Joints in Cables**, state if any, and how made, insulated, and protected Porcelain junction Boxes protected with b.I. covers

**Watertight Glands and Deck Tubes**, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands yes

**Bushes in Beams and Non-watertight Positions**, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed yes state the material of which the bushes are made lead

**Earthing Connections**, state what earthing connections are fitted and their respective sectional areas All W/S Handlamps are earthed by separate conductor having a sectional area of .001 Sq. In. Cargo lights earthed by a separate conductor having a sectional area of .0048 "sq. in." are their connections made as per Rule yes

**Alternative Lighting**, are the groups of lights in the propelling machinery space arranged as per Rule yes

**Emergency Supply**, state position and method of control of the emergency supply and how the generator is driven

**Navigation Lamps**, are these separately wired yes, controlled by separate switch and separate fuses yes, are the fuses double pole yes, are the switches and fuses grouped in a position accessible only to the officers on watch yes

has each navigation lamp an automatic indicator as per Rule yes, are separate screens provided for the use of oil and electric side lights yes, are separate oil lanterns provided for the mast head lights and side lights yes

**Fittings**, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight yes, are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected Strong hinged lead iron covers

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected no, how are the cables led

where are the controlling switches situated —

**Searchlight Lamps**, No. of —, whether fixed or portable —, are their fittings as per Rule —

**Arc Lamps**, other than searchlight lamps, No. of —, are their live parts insulated from the frame or case —, are their fittings as per Rule —

**Motors**, are their working parts readily accessible yes, are the coils self-contained and readily removable for replacement yes, are the brushes, brush holders, terminals and lubricating arrangements as per Rule yes, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material yes

are they protected from mechanical injury and damage from water, steam or oil yes are their axis of rotation fore and aft yes, if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type —, if not of this type, state distance of the combustible material horizontally or vertically above the motors — and —

**Control Gear and Resistances**, are the generator field and motor speed regulators, starters and controllers constructed as per Rule yes

**Lightning Conductors**, where lightning conductors are required, are these fitted as per Rule yes

**Ships carrying Oil having a Flash Point less than 150° F.** Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings —

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office —

**PARTICULARS OF GENERATING PLANT.**

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY.	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	32208	15	100	150	410	Single Cylinder	—	
AUXILIARY	30997	7 1/2	100	75	425	Vertical Steam Engine	—	
EMERGENCY	by Sunderland Forge & Eng Co						—	—
ROTARY TRANSFORMER								

**LIGHTING AND HEATING CONDUCTORS.**

Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Ampères.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	MAIN GENERATOR	2	.1824	37	.14	150	10 ft	V. I. R	Iron pipes
	AUXILIARY GENERATOR	2	.0937	19	.14	75	10 ft	V. I. R	" "
	EMERGENCY GENERATOR								
	ROTARY TRANSFORMER								
	AUXILIARY SWITCHBOARDS								
	ENGINE ROOM								
	BOILER ROOM								
	WIRELESS	2	.0225	7	.064	15	224 ft	V. I. R	Lead covered & Arm'd
	SEARCHLIGHT								
	MASTHEAD LIGHT	1	.002	3	.029	1.2	288 ft		
	SIDE LIGHTS	1	.002	3	.029	1.2	64		
	COMPASS LIGHTS	1	.002	3	.029	.3	30		
	POOP LIGHTS	1	.002	3	.029	.6	35		
	CARGO LIGHTS	1	.007	7	.036	3.0	352		
	ARC LAMPS								
	HEATERS								

**MOTOR CONDUCTORS.**

Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Ampères.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALBAST PUMP								
	MAIN BILGE LINE PUMPS								
	GENERAL SERVICE PUMP								
	EMERGENCY BILGE PUMP								
	SANITARY PUMP								
	CIRC. SEA WATER PUMPS								
	CIRC. FRESH WATER PUMPS								
	AIR COMPRESSOR								
	FRESH WATER PUMP								
	ENGINE TURNING GEAR								
	ENGINE REVERSING GEAR								
	LUBRICATING OIL PUMPS								
	OIL FUEL TRANSFER PUMP								
	WINDLASS								
	WINCHES, FORWARD								
	WINCHES, AFT								
	STEERING GEAR								
	WORKSHOP MOTOR								
	VENTILATING FANS								
	ASH HOIST MOTOR	1	.04	19	.052	50	200 ft	V. I. R	Lead covered & Arm'd
	DUCT KEEL FAN MOTOR	1	.002	3	.029	3	112 ft	V. I. R	

All Conductors are of annealed copper conforming to British Standard Specification No. 7.

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

FURNESS SHIPBUILDING Co. LIMITED

*P. S. Glover*

Electrical Engineers.

Date 18th Nov 1922

COMPASSES.

Distance between electric generators or motors and standard compass 100 ft Approx

Distance between electric generators or motors and steering compass 100 ft -do-

The nearest cables to the compasses are as follows:—

A cable carrying .6 Ampères 3 feet from standard compass 4 feet from steering compass.

A cable carrying .3 Ampères inside feet from standard compass - feet from steering compass.

A cable carrying Ampères feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted yes

The maximum deviation due to electric currents was found to be NIL degrees on ALL courses in the case of the standard

compasses, and NIL degrees on ALL courses in the case of the steering compass.

*J. Mc Govern*  
Director

Builder's Signature.

Date 18th Nov. 1922

Is this installation a duplicate of a previous case Yes If so, state name of vessel 45 "Egyptiana"

General Remarks (State quality of workmanship, opinions as to class, &c.)

*This installation has been efficiently fitted on board and proved satisfactory under working conditions*

It is submitted that this vessel is eligible for THE RECORD. Elec. Light

*A.H.B.*  
18/12/22

Total Capacity of Generators 22½ Kilowatts

The amount of Fee ... £ 18 : 15 : : 8.12.19.22

Travelling Expenses (if any) £ : : See debit book

*Wm Morrison & Wm Cowie*  
Surveyors to Lloyd's Register of Shipping.

TUE. 19 DEC. 1922

Committee's Minute

Assigned

Im. 8.22.—Transfer.  
(The Surveyors are requested not to write on or below the space for Committee's Minute.)



© 2021

Lloyd's Register Foundation