




# Lloyd's Register of Shipping,

47, Quai de la Fosse,

Nantes, 13th January 1932



THE SECRETARY

LONDON

Dear Sir ,

Enclosed please find for approbation by the Committee, plans in triplicate of a proposition to build a second deck in the s/s " CAMBRONNE ", belonging to this port. It is proposed to fit this deck in holds Nos.1,2 and 3.

The owners would like the notation " Second deck fitted" in the case of this vessel, inserted in the Register Book, on completion of the work. in holds Nos.1,2 & 3.

It will be observed that the deck plates are to be lapped, and electric welded with a full weld. This deck has been calculated for a load of 4.000 kilogrammes per m<sup>2</sup>, and is to be 2 m.60 in height.

It will also be observed that extra stanchions are to be fitted below this deck and, in association with a deck girder each side below the hatchways, and extending the whole length of the deck, the double bottom tank will be strengthened to support the stanchions.

Will you kindly return two copies of the plans as soon as possible.

I am , Dear Sir,

Yours faithfully.



Lloyd's Register  
Foundation



Referred to the Chief Ship Surveyor.

15 JAN 1932

REQUESTING EARLY REPLY.

RECEIVED

DEPT. OF COMMERCE

AS SOON AS POSSIBLE.

ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED

DATE 10-10-2001 BY 60322 UCBAW

DATE 10-10-2001 BY 60322 UCBAW

DATE 10-10-2001 BY 60322 UCBAW

DATE 10-10-2001 BY 60322 UCBAW

DATE 10-10-2001 BY 60322 UCBAW

DATE 10-10-2001 BY 60322 UCBAW

DATE 10-10-2001 BY 60322 UCBAW

RECEIVED

DEPT. OF COMMERCE

© 2021

Lloyd's Register  
Foundation