

## FREEBOARD REPORT on the

S. S. GRANDLIEU.

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to

The bunker hatchways on the bridge deck being provided with efficient covers, two tarpaulins & satisfactory battening down arrangements & those on the freeboard deck in the bridge space being provided with efficient covers, one tarpaulin & satisfactory battening down arrangements, if this is not already the case.  
The 3 hatchway in the bridge space being provided with an efficient hatch web, wood covers, satisfactory battening down arrangements & one tarpaulin, as required by the Convention unless the bulkhead at the forward end of the boiler casing extends from side to side of the vessel & is intact or fitted with closing appliances at least equivalent to Class 1.

antes surveys should be requested to furnish particulars of the above hatchways in order to complete their report.  
The freeboards computed under the Convention are in excess of those at present assigned, the latter have been reassigned. 4.1.33