

COPY.

# Lloyd's Register of Shipping,

71, Fenchurch Street, E.C. 3.


25th August, 1920.

Dear Sirs,

I duly received Mr. Mackirdy's letter of the 19th instant submitting for the consideration of the Committee a plan of the pumping arrangements proposed to be adopted in the case of the S.S. No. 101 being built by Messrs. The Coaster Construction Co., Ltd., and with regard thereto I have to acquaint you that provided the sectional area of the fore and after peak tank air pipes be not less than that of their respective falling pipes; an additional steam suction be fitted in the hold, as shewn on plan, a bilge injection and a separate donkey suction, of the size required by the Rules, be fitted in the machinery space; doubling plates be fitted under all sounding pipes, and the arrangements as otherwise shewn on the plan be adhered to and all the work be carried out to your satisfaction, the same will be approved.

The plans forwarded are being returned to you under separate cover.

I have to inform you that it appears that a



© 2020

Lloyd's Register  
Foundation

007045-007053-01462

separate plan of the pumping arrangements in the machinery space has been prepared and a copy of the same should be forwarded for consideration.

I am, Dear Sirs,

Yours faithfully,

Secretary.

The Surveyors,

DUNDEE.



© 2020

Lloyd's Register  
Foundation