

MESSRS. THE COASTER CONSTRUCTION COMPANY, LIMITED.

S.S. NO. 101.

It is submitted that provided the sectional area of the fore and after peak tank air pipes be not less than that of their respective filling pipes; an additional steam suction be fitted in the hold, as shewn on plan, a bilge injection and a separate donkey suction of Rule size be fitted in the machinery space, and doubling plates be fitted under all sounding pipes, this plan of pumping arrangements merits approval.

The Dundee Surveyors should be informed it appears that a separate plan of the pumping arrangements in the machinery space has been prepared and a copy of the same should be forwarded for consideration.

Return 2 plans.

ASR

[Signature]

24.8.20.

C.F.

Ln:- 25/8/20



© 2020

Lloyd's Register
Foundation