

Steel Screw Steamer No. 263 proposed to be built by Messrs.
J. P. Rennoldson & Sons with a view to class 100A1, "For towing
purposes".

Rule Dimensions ; 104.91 x 23 x 13.22

Equipment Number ; 4782

The plans of this vessel were approved on the 6th
instant.

It is now proposed, at the request of the Owners, to
make some alterations to the equipment already approved, and the
equipment as required by Table 22 of the Rules, together with
the altered equipment are as follows, viz:-

<u>As required by Table 22</u>	<u>As desired by the Owners.</u>
1st anchor $6\frac{3}{4}$ cwt. stockless	1st anchor $6\frac{3}{4}$ cwt. stockless
2nd " $5\frac{5}{8}$ " "	2nd " $6\frac{3}{4}$ " "
3rd " $2\frac{1}{2}$ " ex stock	3rd " $1\frac{1}{2}$ " ex stock
	4th " $\frac{1}{2}$ " "
120 fathoms 1" stud chain cable	120 fathoms $\frac{7}{8}$ " stud chain cable
	45 fathoms $9/16$ " stream chain

It will be observed that the collective weight of
the anchors as now proposed is 14 lbs. in excess of that required
by Table 22 of the Rules, and that instead of 90 fathoms of 1"
chain cable it is proposed to supply 120 fms. $\frac{7}{8}$ " chain cable
and 45 fms. $9/16$ " stream chain.

It is submitted that the equipment proposed to be
supplied to the vessel and as desired by the Owners is worthy
of the favourable consideration of the Committee for the figure 1.

TUES. 20 JUL 1909

20.7.09.

$$\begin{array}{r} 11-94 \\ 1-55 \\ \hline 13 \cdot 2 \text{ } 34 \\ 5 \text{ } 34 \\ \hline 12 \cdot 8 \end{array}$$

104.01 x 83 x 13.22 ; 104.01 x 83 x 13.22

© 2021

Lloyd's Register
Foundation

WEB FRAMES, In