

pro Abidela & Mitchell Ltd No 40879 (S.S. Motor Steamers "Indorita" & "Eldorita")


forecastle beams & strengthening of Fore End.

letter has been received from the surveyors stating that
forecastle deck beams have been fitted to alternate frames
instead of to every frame as required for the size fitted.

is submitted the surveyors be informed that, in order to
make the beams equivalent to the rule requirements, a $3 \times 3 \times 30$
inches angle should be fitted to every beam.

a plan of strengthening of fore end forwarded with
a surveyors letter can be approved;

a plan showing the strengthening of the bottom forward of the
 $\frac{1}{5}$ th Length should be forwarded for consideration



© 2021 17.2.21
WJC

Lloyd's Register
Foundation

007439-007447-0120