



# Lloyd's Register of Shipping.

FONDÉ EN 1760. RÉORGANISÉ EN 1834.

RECONNU PAR LA LOI SUR LA SÉCURITÉ DE LA NAVIGATION MARITIME  
(ARRÊTÉ MINISTÉRIEL DU 5 SEPTEMBRE 1908).

188, rue Victor Hugo,

Le Havre, 7th September 1939.

SPECTEURS :  
STRECHMANN.  
MILET.

Dear Sir,

M/V "COTENTIN"

We have to advise that a new spare screw shaft for the above vessel was recently ordered by Owners from the Société Anonyme des Etablissements G. Aubagnac & Cie and made from open hearth steel furnished by the Aciéries Denain, Anzin.

The forging was sent here in agreement with our Paris Office with test pieces attached for the Rule tests to be carried out here by us.

Tests carried out show the following particulars:-

Tensile strength on standard test pieces.

- 27.3 kgs  
(1) 43 Kgs per sq.m/m Elongation 34%.  
(2) 43.1 Kgs " " " Elongation 36%

Cold bent test 180° without sign of fracture.

As the tensile strength is slightly below the Rule minimum of 44 Kgs ( 44 to 63 Kgs ) Owners, especially in view of the difficulties of present circumstances request favourable consideration for acceptance and we shall be glad to have your instructions.

We are, Dear Sir,

Yours faithfully,  
The Surveyors,

The Secretary  
Wokingham.

Per,

*Strechmann*

© 2020  
Lloyd's Register  
Foundation

007714-007721-0243

