

S.S. "ETHELARIC".

IT IS SUBMITTED the freeboards given on the accompanying
Form, being those required by the Tables, merit approval.

Subject to :-

(a) When carrying ordinary cargoes.

1. The Hatch Beam of the poop deck hatch to be made equivalent to the Convention requirements.
2. The coamings of bridge deck ventilators 42" in height to be suitably supported.
3. Efficient means of closing to be provided for the openings of all air pipes, and the airpipes 6" high on the forecastle deck to be provided with nondetachable screw plugs.
4. The doors closing the openings in the bridge fronts to be made capable of being operated from both sides.
5. Gangways, lifelines or other satisfactory means for the protection of the crew to be provided in the wells.

(b) When carrying Timber deck cargoes.

Strong angle or metal sockets or equally efficient means for securing the uprights to be efficiently secured to the stringer plate and spaced not more than 10 ft apart.

Convention
Ordinary and timber deck cargo
Freeboards.

S.B.
25.3.32

Also Lts.
Wm. J. G. G. G.
25/2/32



© 2021

Lloyd's Register
Foundation

007754-007761-0241