

# Lloyd's Register of Shipping.

Order: 11573  
Best: 7401-8

(Report on Machinery, No. \_\_\_\_\_ Port \_\_\_\_\_)

No. 480

## ENGINE FORGINGS OR CASTINGS

I have to report that the Forgings ~~or Castings~~ as herein described, manufactured by Messrs. Gebrüder Böhler & Co. of Kapfenberg for the Engines No. \_\_\_\_\_ being constructed by Messrs. Grazer Waggon-und Maschinenfabrik A.G. of ~~XXXXXX~~ G r a z for the Ship No. 195, being built by Messrs. Stabilimento Tecnico Triestino of T r i e s t e have been inspected by me as set forth below, and found to be, so far as can be seen, sound and free from defects. These have been despatched to Messrs. Stabilimento Tecnico Triestino of T r i e s t e

in Forgings ~~or Castings~~

Reg. Ital.  
Lloyd's

V i e n n a, 30th April 1928

No. 2554 1209-12, 1116-1121

HJ.26.4.28  
20.3.28

*H. Young.*

### Connecting Rods

	<del>CRANK SHAFT</del>	<del>CRANK SHAFT</del>	<del>INTERMEDIATE SHAFT</del>	<del>CRANK SHAFT</del>
	1	1	2	1
	<del>POWELL &amp; COY.</del>			<del>POWELL &amp; COY.</del>
1* ...	Siemens Martin Ingot Steel			
ade ...	forged	forged	forged	forged
illed...	annealed		annealed	
ons, Forgings	3 3/8"	3 3/8" 4 7/16"	4 7/16"	4 7/16"
Castings ...	- - -	- - -	- - -	- - -
on } ction }	finished	finished	finished	finished
n Standard Pieces.	1209	1116	1121 1211/12 1117	1118 1119/20 1210
Test— r square inch	31.4	30.6	29.8 29.9	29.9 30.1 30.1
n per cent	28.6	32.1	32.9 30.1	30.1 31.6 31.6
ding Test— fore fracture	180	d e g r e e g o o d		
en Inspected	18.11; 5.10 1927 2.2; 20.3; 26.4.1928			


### PARTICULARS OF OTHER TESTS APPLIED TO ~~CASTINGS~~

ew bolts, 2 1/16" Tens.str.in t/sq" 28.8 with 37.0 % elong.in 3"  
" " 1 3/4" " 28.0 " 36.0  
" " " 28.0 " 36.8 %  
Bend tests good

any chargeable) £

To be paid at VIENNA

wrought iron, state whether piled bars or scrap. If of steel, state whether made by the Open Hearth process.



© 2020

Lloyd's Register  
Foundation