

As a C. S. S.
Lloyd's Register of Shipping.
SURVEYS FOR FREEBOARD.

PARTICULARS IN RESPECT OF STEAM SHIPS HAVING SPAR OR AWNING DECKS.

Port of Survey _____
Date of Survey 6/2/25
Name of Surveyor _____

Canadian Nav. Institute M.V. Nos. 155, 156 + 157
same as

| | | | | | |
|--------------|-----------------------------------|------------------|----------------|----------------|--------------------------------|
| Ship's Name. | Port of Registry and Nationality. | Official Number. | Gross Tonnage. | Date of Build. | Particulars of Classification. |
| | <i>NO 158</i> | | | | |

| | | | | |
|--------------------------------------|--------------|------------------|---------------|---------------------|
| Registered Dimensions from Register. | LENGTH. | BREADTH. | DEPTH. | UNDER DECK Tonnage. |
| Length on LOADLINE | | Frame Depth Rule | Ceiling Sheer | Peak Tanks |
| CORRECTED DIMENSIONS. | <i>400.0</i> | | | |

Moulded Depth as measured *27-10* Main Deck.
" " " *35-10* Spar or Awning Deck.

Height of Tween Decks are equal to Standard, viz. 8-0

Addition for Keel below base line for draught record.....inches.

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

Co-efficient of fineness
Any modification necessary }
[Para. 4 (a) to (e)*] }
Co-efficient as corrected

.78 provisionally

Allowance for strength in excess of Lloyd's rules =

State particulars—

CORRECTION FOR LENGTH:—

Length of Ship on Load Line..... *400.0*
Length in Table *334.0*
Difference..... *66.0*
Correction for 10ft..... *1.7*
× Difference ÷ 10 = *4.62*
+ 4 1/2"

Height of 'Tween Decks..... *8-0*
(From top of beam to top of beam at side)
Correction for Height of 'Tween Decks in Spar-decked Ships.....

Freeboard Table B or C *3" 7 1/4*
Correction for Length..... *+ 4 1/2*
3" 11 3/4
Correction for Height of 'Tween Decks in Spar-decked Ships..... *8-0*
11" 11 3/4

Correction for Strength in excess of Lloyd's rules.....

Correction for Iron Deck if required..... *— 3 1/2*
11" 8 1/4

Other Corrections (if any).....

Winter Freeboard..... *11" 8 1/4*
Summer Freeboard *5 1/2* *11" 2 3/4*
Indian Summer Freeboard.....
N. A. Winter Freeboard.....

Correction necessary because clearside amidships measured in accordance with the Statute is not taken at inter-section of the wood or steel deck with side

35-10 1/2
11-2 3/4
24-7 3/4
ml

Winter Freeboard from Deck Line
Summer " " "
Indian Summer " " "
N.A. Winter " " "

Sheer at Stem at $\frac{1}{8}$ length from Stem
Sternpost... " " " Sternpost...
Drop in Sheer abaft amidships.....

Round of Spar-deck Beam.....
" " Main-deck "

| | | | | |
|------------------|--------|---|---------|----------------------------------|
| | Length | × | Height. | State if open or closed at ends. |
| Forecastle | | × | | |
| Bridge..... | | × | | |
| Coop..... | | × | | |

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Steel) Deck:—

| | | | | | | | | | |
|----------------------------|----------------------|-----|-----|-----|-----|-----|-----|-----|-----|
| Fresh Water Line | above centre of Disc | ... | ... | ... | ... | ... | ... | ... | ... |
| Indian Summer Line | " | " | " | ... | ... | ... | ... | ... | ... |
| Winter Line | below | " | " | ... | ... | ... | ... | ... | ... |
| Winter North Atlantic Line | " | " | " | ... | ... | ... | ... | ... | ... |

NOTE.—All vessels equal in strength to Lloyd's Spar-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for Ships of full scantlings to the upper deck, are to be considered as Spar-decked Ships, the freeboard for which will vary with their strength.
All vessels equal in strength to Lloyd's Awning-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for a Spar-decked Vessel, are to be considered as Awning-decked Ships, the freeboard for which will vary with their strength.

* If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.