

(Freeboards assigned under the provisions of the U. S. A. Load Line Act of March 2, 1929.)

When received in New York Office.....22 DEC 1930

When received in New York Office..... 22 DEC 19

Port..... MOBILE, ALA.

Name of Vessel..... S. S. "H. M. FLAGLER"

Official No. 216456 No. in Reg. Book .. 72529

Port of Registry .. WILMINGTON State whether classed by Lloyd's Register.. YES

Name of Owners .. STANDARD SHIPPING CO Date of Verification .. 27TH OCT. 1930

I have to report that the freeboard from the centre of disc to the top of the deck, and the lines in connection therewith, as given below, assigned by the American Committee to this vessel, have been correctly marked on the vessel's sides, in accordance with the printed instructions and that all the conditions of assignment have been complied with:—

	Freeboard from Deck line	Load line
Summer in Tropical Seas (T)	9 ft. 7 $\frac{3}{4}$ ins.	(a) 6 $\frac{3}{4}$ ins. above centre of disc
Summer (S)	10 ft. 2 $\frac{1}{2}$ ins.	(b) Upper edge of line through centre of disc.
Winter (W)	10 ft. 9 $\frac{1}{4}$ ins.	(c) 6 $\frac{3}{4}$ ins. below centre of disc
Winter North Atlantic (WNA)	11 ft. 1 $\frac{3}{4}$ ins.	(d) 11 $\frac{1}{4}$ ins. below centre of disc
Load line for fresh water for Summer and Tropical Summer (F and TF) above top respective lines	7 $\frac{1}{2}$ ins.	

the top of the deck line is set off in relation to the top of the $\left\{ \begin{array}{c} \text{steel} \\ \text{wood} \end{array} \right\} \left\{ \begin{array}{c} \text{upper} \\ \text{shelter} \end{array} \right\}$ deck.


NOTE: FREEBOARDS ASSIGNED BY THE AMERICAN BUREAU OF SHIPPING.

Timber Load Lines (where Applicable)

	Freeboard from Deck line	Load line
Summer in Tropical Seas (LT).....ft.ins.ins. above centre of disc	
Summer (LS).....ft.ins.ins. above centre of disc	
Winter (LW).....ft.ins.ins. {above below} centre of disc	
Winter North Atlantic (LWNA).....ft.ins.ins. below centre of disc	
Load line for fresh water for summer and Tropical summer (LF and LTF) above top respective linesins.		

Surveyor to Lloyds Register of Shipping.

Noted WED
22.12.30



© 2020

Lloyd's Register
Foundation