

G.R. 130.

Classed
8554 = an. p. 85

(LLOYD'S REGISTER.)**VESSELS OF 100 TONS AND UPWARDS.**

Three

9.10.44



These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping
Signal Letters (if any).....U.D.D.R.....

Official Number.	Name of Ship.	No., Date, and Port of Registry.
175,387	CONFEDERATION PARK	33-1944 Montreal, Que.

No., Date, and Port of previous Registry (if any). First Registry

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Screw	Pictou, N.S.	1944	Foundation Maritime Limited, Pictou, N.S.

Number of Decks One	Length from fore part of stem, to the aft side of the head of the stern post	Feet.	Tenths.
Number of Masts Two		315	5
Rigged Not	Main breadth to outside of plank	46	5
Stem Raked	Depth in hold from tonnage deck to ceiling amidships	22	9
Stern Cruiser	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards	-	-
Build In & Out	Depth from top of deck at side amidships to bottom of keel...	25	2
Framework and description of vessel Steel Cargo	Round of beam	-	9
Number of Bulkheads	... 5 W.T.	Length of engine room, if any	44	-

Particulars of propelling Engines, etc. (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines	Description of Engines	Whether British or Foreign Made	When made	Name and address of makers	Reciprocating Engines		Rotary Engines	N.H.P. B.H.P. I.H.P. Estimated Speed of Ship
					No. and Diameter of Cylinders in each set	Length of Stroke	No. of Cylinders in each set	
One	Reciprocating Triple Expansion	Engines British	Engines 1944	Engines Canada Iron Foundries Ltd., Three Rivers, Que.	THREE 20"	39"	-	N.H.P. 146 I.H.P. 1176
No. of Shafts	Particulars of Boilers				31"			
One	Description... Scotch Number... Two Iron or Steel... Steel Loaded Pressure... 200 #	Boilers British	Boilers 1944	Boilers Dominion Bridge Coy. Ltd., Montreal, Que.	55"			10-11 knots

Number of water ballast tanks, and their capacity in tons:— SIX — 737 tons.

008158-008167-0027

[P.T.O.]

Gas. H. Name

© 2021
Lloyd's Register
Foundation

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	2515.07 ✓	On account of space required for propelling power	920.98
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind not being the personal property of the Crew.	
Turret or Trunk	7.20	These spaces are the following, viz. :—	
Forecastle	9.25	Poop 80.16	
Bridge space	41.70	Deck Houses 130.50	210.76
Poop or Break	85.47	(Number of Seamen or Apprentices for whom accommodation is certified.....43.....)	
Side Houses	42.09	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :—	
Deck Houses	107.58	Cubic Meters. Master Accom 9.36)	
Chart House	6.18	Chart Room 6.18)	
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		Gyro Compass Room 4.32)	93.51
Excess of Hatchways	63.52	W.T. Room 8.18)	
		B'swain Stores 14.90)	
		Water Ballast 50.57)	
		Total	1225.25
Gross Tonnage	2878.06 ✓		
Deductions, as per contra	1225.25		
Register Tonnage	1652.81 ✓		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 376.99 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 89.82 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Galley 9.22; Wheelhouse 7.70; Steering Gear 17.33; Refrigerator 7.38;

Toilets 5.88; Open Bridge 192.64; Open Focs'le 43.40; Light & Air 39.82 tons.

Name of Master

Certificate of { Service No.
Competency No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

His Majesty the King, in right of Canada, represented by the Honourable the Minister of Munitions and Supply, of the Dominion of Canada, for the time being, Ottawa, Ont.

Park Steamship Company, Limited, of 410 St. Nicholas Street, Montreal, Que.

Sixty-four (64) shares.

Designated Managers.

Dated Montreal, Que. May 2nd 1944.