

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

Handwritten initials

36
6
4
6
16

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.
Signal Letters (if any) G.Z.D.L

Official Number.	Name of Ship.	No., Date, and Port of Registry.
164,303.	Dorset Coast.	32/1936 Liverpool.

No., Date, and Port of Previous Registry (if any). -----

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Motorship Single Screw.	Ardrossan	1936	Ardrossan Dockyard Co., Ltd., Ardrossan.	
Number of Decks	Two	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post	Feet.	Tenths.	
Number of Masts	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel	199	4.0	
Rigged	Not rigged	Main breadth to outside of plank-plating	206	0.0	
Stern	Cruiser	Depth in hold from tonnage deck to ceiling at midships	33	1.5	
Build	In and Out	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards	11	1.0	
Galleries	None	Depth from top of beam amidships to top of keel	21	9.2	
Head	None	Depth from top of deck at side amidships to bottom of keel	21	3.3	
Framework and description of vessel	Steel Cargo Vessel	Round of beam	---	---	
Number of Bulkheads	Three	Length of engine room, if any	52	2.2	
Number of water ballast tanks, and their capacity in tons	Five - 248 tons.				

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel 2080 Tons. Ditto per inch immersion at same depth 13 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Internal Combustion Diesel.	Engines. British	Engines. 1936	Engines. J.G. Kincaid & Co., Ltd., Greenock.	Six 500 m/m	900 m/m		116.19 1000 (Estimated) 1275 (Estimated)
No. of Shafts.	Particulars of Boilers.	Boilers.	Boilers.	Boilers.	Four Stroke Cycle			11 knots (Estimated)
One	Description Number Iron or Steel Loaded Pressure	-----	-----	-----	Single Acting 168 revs per min.			

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck		499.49	On account of space required for propelling power		286.44
Space or spaces between Decks			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		71.22
Turret or Trunk			These spaces are the following, viz. :- Poop, Bridge and Round House		
Forecastle		5.36	(Number of Seamen or Apprentices for whom accommodation is certified)		
Bridge space		39.92	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :-		
Poop or Break		29.01	Master's Accomdn. 5.13		
Side Houses			Chart Space 3.62		
Deck Houses		22.56	Boatswain's Store 7.45		44.42
Chart House		3.62	Dynamo for S.S. Gear 1.44		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		41.23	Water Ballast Spaces 26.78		
Excess of Hatchways		4.67	Total		402.08
Gross Tonnage		645.86			
Deductions, as per Contra.		402.08			
Register Tonnage		243.78			

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 122.45 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 90.33 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Top Gallant Forecastle	= L. 22.3'	= 15.91 tons.
In Tween Deck Part I	= L. 122.0'	= 292.02 tons.
Do Part II	= L. 4.0'	= 10.48 tons.


Name of Master _____ Certificate of { Service No. Competency No. _____

No. of Owners _____

Name, Residence, and Description of Managing Owner if there are more owners than one.

Coast Lines Limited
London House,
3, New London Street, London,
Sixty-four shares.

Dated 20th October 1936.



© 2020
Lloyd's Register
Foundation

608201-008210-0131