

28 OCT 1936

Rpt. 13.

No. 57496

REPORT ON ELECTRICAL EQUIPMENT.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office

Date of writing Report 20 October 1936 When handed in at Local Office 24. 10. 1936 Port of Glasgow.

No. in Survey held at Adrossan Date, First Survey 20. 10. 36 Last Survey 22. 10. 1936
 Reg. Book. 74142 on the M.V. 'DORSET COAST' (Number of Visits 3)

Tons { Gross 646
 Net 244

Built at Adrossan By whom built Adrossan Dockyard Ltd Yard No. 363 When built 1936

Owners Coast Line Ltd. Port belonging to Liverpool

Electric Light Installation fitted by Campbell & Johnson Ltd Contract No. 363 When fitted 1936

Is the Vessel fitted for carrying Petroleum in bulk no.

System of Distribution Two wire

Pressure of supply for Lighting 220 volts, Heating — volts, Power 220 volts.

Direct or Alternating Current, Lighting Direct Power Direct

If alternating current system, state frequency of periods per second —

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes

Generators, do they comply with the requirements regarding temperature rise Yes, are they compound wound Yes
 are they over compounded 5 per cent. Yes, if not compound wound state distance between each generator —

Where more than one generator is fitted are they arranged to run in parallel Yes, is an adjustable regulating resistance fitted in series with each shunt field Yes Have certificates of test results for machines under 100 kw. been submitted and approved Yes Have machines over 100 kw. been inspected by the Surveyors during manufacture and testing —

Are all terminals accessible, clearly marked, and furnished with sockets Yes, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched Yes Are the lubricating arrangements of the generators as per Rule Yes

Position of Generators In main Engine Room. is the ventilation in way of the generators satisfactory Yes are they clear of all inflammable material Yes if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators — and — are the generators protected from mechanical injury and damage from water, steam or oil Yes, are their axes of rotation fore and aft Yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes are the prime movers and their respective generators in metallic contact Yes Main Switch Boards, where placed In Engine Room near generators.

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard —

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes, are they protected from mechanical injury and damage from water, steam or oil Yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards — and —, are they constructed wholly of durable, non-ignitable non-absorbent materials Yes, is all insulation of high dielectric strength and of permanently high insulation resistance Yes, is it of an approved type Yes, if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework Sindango. is the non-hygroscopic insulating material of an approved type Yes, and is the frame effectively earthed Yes Are the fittings as per Rule regarding:— spacing or shielding of live parts Yes, accessibility of all parts Yes, absence of fuses on back of board Yes, temperature rise of omnibus bars Yes, individual fuses to voltmeter, pilot or earth lamp Yes, are moving parts of switches alive in the "off" position no are all screws and nuts securing connections effectively locked Yes are any fuses fitted on the live side of switches no.

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches D.P. circuit breaker with 1/2 & 1/4 trip, auto locked equaliser switch for each generator, S.P. switch & D.P. fuses for each outgoing circuit

Are turbine driven generators fitted with emergency trip switch as per rule — Are cupboards or compartments containing switchboards composed of fire-resisting material or lined with approved material — Instruments on main switchboard 3 ammeters 2 voltmeters — synchronising device for paralleling purposes. For compound machines is the ammeter connected on the opposite pole to equaliser connection Yes

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system Earth Lamps. Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules Yes are the fusible cutouts of an approved type Yes have the reversed

28 OCT 1936

current protection devices been tested under working conditions Yes Joint Boxes, Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule Yes

Cables: Single, twin, concentric, or multicore Single & Twin are the cables insulated and protected as per Tables IV, V, X or XI of the Rules Yes

If the cables are insulated otherwise than as per Rule, are they of an approved type 3 Volls Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load Yes Cable Sockets, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets Yes Paper Insulated and Varnished Cambric Insulated Cables.

If conductors are paper or varnished cambric insulated, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound Yes, or waterproof insulating tape Yes Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage Yes Are cables in machinery spaces, galleys, laundries, bathrooms and lavatories lead covered or run in conduit Yes to R.R.

Support and Protection of Cables, state how the cables are supported and protected Main R. R. braked in Galval tubing heavy spec. L.C. R. clipped on R.R. in tubing, Accommodation R.R. clipped.

If cables are run in wood casings, are the casings and caps secured by screws Yes, are the cap screws of brass Yes, are the cables run in separate grooves Yes If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII Yes

Refrigerated Chambers, are the cables and fittings in accordance with the special requirements None

Joints in Cables, state if any, and how made, insulated, and protected None

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands Yes Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed Yes state the material of which the bushes are made Lead

Earthing Connections, state what earthing connections are fitted and their respective sectional areas Lead covering & earthing of cables, braked & earthed. are their connections made as per Rule Yes

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule Yes Emergency Supply, state position and method of control of the emergency supply and how the generator is driven Yes

Navigation Lamps, are these separately wired Yes, controlled by separate switch and separate fuses Yes, are the fuses double pole Yes are the switches and fuses grouped in a position accessible only to the officers on watch Yes has each navigation lamp an automatic indicator as per Rule Yes Secondary Batteries, are they constructed and fitted as per Rule Yes

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight Yes are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected Yes - protected by strong glass & metal guards. are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected Yes how are the cables led Yes

where are the controlling switches situated Yes are all fittings suitably ventilated Yes, are all switches and lampholders constructed wholly of non-ignitable, non-absorbent materials Yes

Heating and Cooking Appliances, are they constructed and fitted as per Rule Yes, are air heaters constructed and fitted as per Rule Yes

Searchlight Lamps, No. of Yes, whether fixed or portable Yes, are their fittings as per Rule Yes

Are Lamps, other than searchlight lamps, No. of Yes, are their live parts insulated from the frame or case Yes, are their fittings as per Rule Yes

Motors, are their working parts readily accessible Yes, are the coils self-contained and readily removable for replacement Yes are the brushes, brush holders, terminals and lubricating arrangements as per Rule Yes, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material Yes are they protected from mechanical injury and damage from water, steam or oil Yes are their axes of rotation fore and aft Yes - on vertical if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type Yes if not of this type, state distance of the combustible material horizontally or vertically above the motors Yes and Yes

have machines of over 100 BHP been inspected by the Surveyors during manufacture and testing Yes Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule Yes Lightning Conductors, where lightning conductors are required, are these fitted as per Rule Yes Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings Yes are all fuses of the filled cartridge type Yes are they of an approved type Yes

If portable lamps for use in dangerous spaces are supplied, are they of a self-contained, battery-fed type approved by the Home Office Yes

Spare Gear, if the vessel is for open sea service have spares been supplied as per Rule Yes

PARTICULARS OF GENERATING PLANT.									
DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.		
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.	
MAIN ...	3	40	220	182	1000	Oil Engine	Diesel Oil	Above 150° F.	
AUXILIARY ...									
EMERGENCY ...									
ROTARY TRANSFORMER									

GENERATOR, LIGHTING AND HEATING CONDUCTORS.									
DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Nominal Area per Pole Sq. Ins.	No.	Diameter.	Circuit.	Rule.			
MAIN GENERATOR ...	2	15	19	0.072	182	194	444	Rubbers	L.C.A.B.
EQUALISER CONNECTIONS ...	1	0.75	19	0.072	-	97	22	"	" "
AUXILIARY GENERATOR ...									
EMERGENCY GENERATOR ...									
ROTARY TRANSFORMER } MOTOR GENERATOR...									
ENGINE ROOM... D.B.	1	0.03	3	0.036	3	12	12	"	H.R. Brakel
BOILER ROOM... ..									
AUXILIARY SWITCHBOARDS ...									
Lighting Set Box.	1	0.01	7	0.044	26	31	90	"	L.C.A.B.
ACCOMMODATION									
Navigation D.B.	1	0.03	3	0.036	3.5	12	280	"	H.R. Brakel
Hotel Power D.B.	1	0.03	3	0.036	5	12	6	"	" "
WIRELESS	1	0.07	7	0.036	15	24	280	"	" "
SEARCHLIGHT	1	0.03	3	0.036	18	12	300	"	" "
MASTHEAD LIGHT	1	0.03	3	0.036	18	12	40	"	H.R. Brakel
SIDE LIGHTS	1	0.03	3	0.036	10	12	140	"	" "
COMPASS LIGHTS	1	0.03	3	0.036	4.5	12	12	"	H.R. Brakel
POOP LIGHTS	1	0.03	3	0.036	4.5	12	12	"	H.R. Brakel
CARGO LIGHTS									
ARC LAMPS									
HEATERS									

MOTOR CONDUCTORS.										
DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Nominal Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP	1	1	0.07	7	0.036	18	24	34	Rubbers	L.C.A.B.
MAIN BILGE LINE PUMPS										
GENERAL SERVICE PUMP ...	1	1	0.07	7	0.036	18	24	56	"	" "
EMERGENCY BILGE PUMP ...										
SANITARY PUMP										
CIRC. SEA WATER PUMPS ...										
CIRC. FRESH WATER PUMPS...										
AIR COMPRESSOR	2	1	0.03	19	0.044	55	53	22	"	" "
FRESH WATER PUMP										
ENGINE TURNING GEAR...	1	1	0.045	7	0.029	16.7	18.2	60	"	" "
ENGINE REVERSING GEAR ...										
LUBRICATING OIL PUMPS ...	1	1	0.03	19	0.052	62	64	20	"	" "
OIL FUEL TRANSFER PUMP ...	1	1	0.04	19	0.052	67.5	68	12	"	" "
WINDLASS	1	1	0.15	37	0.072	105	152	230	"	H.R. Brakel
WINCHES, FORWARD	2	1	0.10	19	0.053	105	118	60	"	" "
" "	1	1	0.15	37	0.072	105	152	110	"	" "
WINCHES, AFT	1	1	0.04	19	0.052	67.5	68	210	"	" "
Capstan										
STEERING GEAR—										
(a) MOTOR GENERATOR...										
(b) MAIN MOTOR	1	1	0.01	7	0.044	25	31	180	"	H.R. Brakel
WORKSHOP MOTOR										
VENTILATING FANS										
Sub. Oil Pump	1	1	0.003	3	0.036	3.5	12	40	"	" "
Power Section Box "S"	-	1	0.12	37	0.064	126	130	100	"	L.C.A.B.
" Dist. Box 601	-	1	0.075	19	0.072	95	97	110	"	" "
" " 602	-	1	0.07	7	0.036	18	24	30	"	" "
" 603 Dist. Box	-	1	0.20	37	0.043	195	247	340	"	H.R. Brakel

All Conductors are of annealed copper conforming to British Standard Specification No. 7 (or International Electro-technical Commission Publication No. 28).

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

CAMPBELL & ISHKEWOOD, LTD.

Electrical Engineers.

Date 21. 10. 36.

COMPASSES.

Distance between electric generators or motors and standard compass

160 ft

Distance between electric generators or motors and steering compass

160 ft

The nearest cables to the compasses are as follows:—

A cable carrying 10 Ampères 6 ft from standard compass 6 feet from steering compass.

A cable carrying 10 Ampères 6 feet from standard compass 6 ft from steering compass.

A cable carrying 3.5 Ampères 8 feet from standard compass 7 feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power. Yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted. Yes

The maximum deviation due to electric currents was found to be 1/2 degrees on any course in the case of the standard compass, and 1/2 degrees on any course in the case of the steering compass.

FOR ARROSSAN DOCKYARD, LIMITED.

John C. Colman

Builder's Signature.

Date

23/10/36

Is this installation a duplicate of a previous case. Yes If so, state name of vessel M.V. 'DEVON. COAST.'

General Remarks (State quality of workmanship, opinions as to class, &c. The electrical equipment of this

vessel has been fitted on board under special survey, tested under full working conditions and found satisfactory. The materials and workmanship are good and sound.

24/10/36.

Wid

Run

29.10.36

Total Capacity of Generators 120 Kilowatts.

The amount of Fee ... £ 34. 10 : 027 OCT 1936

Travelling Expenses (if any) £ : 9 : 29.10.36

Surveyor to Lloyd's Register of Shipping.

Committee's Minute GLASGOW 27 OCT 1936

Assigned SEE ACCOMPANYING MACHINERY REPORT.

2m. 5.34. Transfer.

The Surveyors are requested not to write on or below the space for Committee's Minute.)



© 2020

Lloyd's Register
Foundation