

COPY

Rpt. C. 11 (Contd.)

Index No.

# Lloyd's Register of Shipping.

Ship's Name "INCHWELLS"

Official No. 167590

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

## Superstructure Bulkheads : -

Poop. Original closing appliances removed and replaced by two hinged steel W.T. doors, 1 port, 1 starboard, strongly framed, opening 2'-2" x 5'-0", sills 16".

Doors capable of being operated from both sides. ✓

## Ventilators : -

Bridge Deck. One ventilator 10" dia., coaming 23" high, previously installed, fitted with wood plug and canvas cover.

Two mushroom type ventilators, port side, 9" dia., coaming 9" high, steel W.T. covers, previously installed. ✓

## Forecastle Deck.

Twelve mushroom type ventilators, 9" dia., coaming 9" high, steel W.T. covers, previously installed. ✓

## Poop Deck.

Three ventilators previously installed.


Two 9½" dia., coaming 2'-6", one 15" dia., coaming 1'-6". All fitted with wood plugs and canvas covers. ✓

*Samuel Anderson*  
Surveyor to Lloyd's Register.

HONG KONG.

23rd April, 1951.

*Patent*  
*Adm.*



© 2020

Lloyd's Register  
Foundation