

Received by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

VESSEL'S NAME s.s. "EMPIRE MOULMEIM" Rpt. Nwc. No. 102296

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement." - Extract from Sub-Committee's Report, 24/5/92.)

D to W dk 37.67' (flat sheer), D to 2nd dk 28.67' (flat sheer), D for scantlings 35.75' to normal Sheer.

1st Long. No. 15194) Depth "d" -
) to normal sheer
2nd Long. No. 38994) Proportions = L/D 11.27

Framing as approved Sheerstrake as approved

This partly fabricated Standard Ship Type "B" is similar to the "EMPIRE PERDITA", "EMPIRE PICKWICK" etc.

The draught is about 6" less than that corresponding to the freeboard which could be assigned as a F.S. vessel.

The tank top plating increased under hatchways in lieu of ceiling. This vessel appears to have been built in accordance with the

Rules and the approved plans, and it is submitted she is eligible to be classed *100A1 "With freeboard"

The Summer Freeboard as shown on the attached extract from the Freeboard Verification Form, now marked on the vessel's sides, to be inserted in the classification certificate and recorded in the Register Book, and further, the remaining freeboards, as shown on the accompanying extract, to be inserted in the certificate of classification.

2 Dks Cell DB 318' 1270t, tank in way of tunnel 345t, wing tanks fwd 250t, FPT 153t APT 105t

FK, 7 BH (Coll to W dk, 6 to 2nd dk), 6 divisional W.T. BHs in 'tween decks, pt. Cem., Lloyd's A & CP

O.L. 446.4' of Anchors
E.S.D. The class is assigned and maintained upon the understanding that the equipment will be
a made to accord with the requirements of the Rules when the present state of emergency
2 has passed, and that cargo battens will be fitted at the first available opportunity.

Insert in S.R.L.- (A bower anchor to be supplied)
Cargo battens to be fitted at the first opportunity.



© 2021

Lloyd's Register Foundation 31.8.14

008237-008247-0095