

COPY. *for Trieste*

Lloyd's Register of Shipping.

Port of Genoa,

September 10th, 1928 . .

MV Fusijama STT 773
Trieste Rn 8341

This is to Certify that

A. S. MANTELLI

the undersigned Surveyor to this Society did at the request of Messrs Società Anonima TRAFILERIE E CORDERIE ITALIANE of Milan, attend on the August 6th 1928 and subsequent dates, at their Works of Sesto San Giovanni (Milan), for the purpose of examining and testing 2(two) Coils of galvanised steel wire ropes intended for Messrs STABILIMENTO TECNICO TRIESTINO - Trieste - (order N°3312/3 dated 26/5/28).

For particulars of the steel wire ropes & Statutory tensile load applied, see below : -

	<u>Arc 127</u>	<u>Arc 133</u>
N° of Coils	= 1	1
Length in Mt.	= 165	238
Diametres	= 40.5 m/m.	42.5 m/m.
N° of strands	= 6	6
N° of cores	= 7	7
N° of wires	= 72	72
Diametre of wires	= 2.70 m/m.	2.80 m/m.
Tensile load specified ..	= 59940 Kgs.	66040 Kgs.
Tensile load obtained ...	= 62937 Kgs.	69342 Kgs.
Twisting test	= Good	Good.

For purpose of identification, lead seals marked BSM have been attached to the coils.

A. Mantelli

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—
"While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for accuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of the Surveyors, or other Officers or Agents of the Society."