

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

G.R. 130.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.

Signal Letters (if any) **G. W. W. Q.**

Official Number.	Name of Ship.	No., Date, and Port of Registry.
164,039.	Tynebank.	35/1934 Glasgow.

No., Date, and Port of Previous Registry (if any). -----

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw.	South Shields.	1934	John Readhead & Sons Ltd. South Shields.

Number of Decks ..	One & Shelter	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ..	Feet.	Tenths.
Number of Masts ..	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ..	412	9
Rigged ..	Schooner	Main breadth to outside of plank ..	54	0.5
Stem ..	Elliptical	Depth in hold from tonnage deck to ceiling at midships ..	24	0.5
Build ..	Clincher	Depth from top of beam amidships to top of keel ..	28	1
Galleries ..	None	Depth from top of deck at side amidships to bottom of keel ..	27	3
Head ..	Straight	Round of beam ..	1	0
Framework and description of vessel ..	Steel Cargo Vessel	Length of engine room, if any ..	47	5
Number of Bulkheads ..	Seven			
Number of water ballast tanks, and their capacity in tons ..	Eight -1596 Tons.			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel: **9690** Tons. Ditto per inch immersion at same depth: **43.4** Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
Three	Reciprocating Triple Expansion Direct Acting Inverted.	Engines.	Engines.	Engines.	Three			524
		and	and	and	25"			---
	Particulars of Boilers.				42"	48"	----	2800
	Description: Cylindrical Multitubular	Boilers.	Boilers.	Boilers.	71"			
	Number: Two	British	1934	John Readhead & Sons Ltd., South Shields.				12 Knots
	Iron or Steel: Steel							
	Loaded Pressure: 220 lbs per sq. in.							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ..	4243.88	On account of space required for propelling power ..	1488.25
Space or spaces between Decks ..		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew ..	269.30
Trunk House in Shelter Deck ..	28.71	These spaces are the following, viz.:— In Poop, Roundhouses and Sidehouses.	
Forecastle (Lower Upper Houses in ..	28.56	(Number of Seamen or Apprentices for whom accommodation is certified ..)	
Edge space ..	17.22	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Open Break ..	129.16	Master's Accommodation 18.14)	
Life Houses ..	5.52	Chart Space 4.89)	161.62
Cook Houses ..	192.85	Wireless Telegraphy Space 4.70)	
Part House ..	4.89	Boatswain's Storerrooms 46.51)	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ..		Water Ballast Spaces 87.38)	
Access of Hatchways ..		Total ..	1919.17
Gross Tonnage ..	4650.79	Cubic Metres.	
Deductions, as per Contract ..	1919.17	13161.74	
Register Tonnage ..	2731.62	5431.26	
		7730.48	

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is **646.53** tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is **138.83** tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.


Shelter Tween Deck Part I Length 178.3 feet	-	693.12 tons.
II "	47.5 "	135.33 "
III "	122.5 "	529.65 "
IV "	9.9 "	39.17 "
Forecastle Length 30.6 "	-	41.89 "

Name of Master	Certificate of	Service No.	Competency No.
----------------	----------------	-------------	----------------

Name, Residence, and Description of Managing Owner if there are more owners than one.

The Bank Line Limited
102 Hope Street, Glasgow. C.2.
Sixty-four Shares - 64-

Hon. Andrew Alexander Morton Weir
of same address
- Manager -



30 Oct. 1934.