

SHELTER DECK FREEBOARD.

EQUIPMENT

2 BOWER ANCHORS, STOCKLESS, EACH 25 $\frac{1}{2}$ CWTs
1 BOWER ANCHOR STOCKLESS, 25 $\frac{1}{2}$ CWTs
1 STREAM ANCHOR, STOCKLESS, 8 CWTs
210 FATHOMS 1 $\frac{1}{2}$ " STUD LINK CABLE
75 FATHOMS 3 $\frac{1}{2}$ " CIRC. F.S.W.R. (6"12) STREAM
90 FATHOMS 3 $\frac{1}{4}$ " CIRC. F.S.W.R. (6"12) TOWLINE
90 FATHOMS 6" CIRC. HEMP HAWSER
90 FATHOMS 5" CIRC. HEMP WARP

STEM BAR $7" \times 1\frac{3}{4}"$

"B" CLASS COASTERS

LLOYDS NUMERALS

L =	210.0 FT.
B =	36.5 FT.
D =	21.58 FT.
d =	11.38
$\frac{L}{D} = \frac{210.0}{21.58}$	9.7

1ST NUMERAL
$$L \times D = 210.0 \times 21.58 = 4531.8$$

2ND NUMERAL

$$L \times (B+D) = 210.0 \times 58.08 = 12,196.8$$

EQUIPMENT NUMERAL

$L \cdot (B+D) = 210.0 \times 58.17 = 12216.0$
 FORECASTLE $27.5 \times 70 \times .75 = 144.4$
 MIDSHIP D.K.HSE. $27.0 \times 8.0 \times .50 = 108.0$
 AFTER D.K.HSE. $52.0 \times 7.5 \times .5 = 195.0$
 EQUIPMENT NUMERAL : $= 12.66$

SHIP	42
MIDSHIP SECTION AS FITTED	
CLASS "B" COASTER (STEAM)	
SCALE $\frac{1}{2}$ " = 1'-0"	DRAWING NO.
DRAWN BY: J. C. G. L.	1063
CHECKED BY:	
APPROVED BY: J. A. Gilbert.	DATE DEC. 16, 1945
Victoria Machinery Depot Co. Ltd. Victoria, B. C.	