

BREADTH MOULDED	52'0"
DEPTH MOULDED	31'0"
	83'0"
LENGTH	400'0"
	33200 -
$\frac{1}{2}$ TO UPPER DECK =	12'90"
$d =$	27'5"

2 BOWER ANCHORS	60 CWTs	STOCKLESS
1 " "	50 1/2 "	" "
1 STREAM "	16 1/4 "	EX STOCK
210 FATHOMS	2 3/8" STUD LINK CHAIN CABLE	
90 "	1 1/4" STREAM CHAIN, OR	4 3/4" SWROPE
120 "	14 HEMP HAWSERS, OR	4 3/4" "
2 OFF 90 "	8" HEMP HAWSERS, OR	2 3/4" "
2 OFF 90 "	7" "	WARPS, OR 2 1/2" "
1 KEDGE ANCHOR	7 CWTs	EX STOCK

HULL 400 (52+31)	33200
POOP, BRIDGE & F'CLE, 200'x8'x75' =	1200
DECK HOUSE 31.5'x75'x5'	118
	<u>34518</u>

22.3.19.

No. 673 Lloyd's Re

004 741 008 414 21 80

Miss^{rs} Richardson Dock W^g!

N^o 675

M^{rs}: Sec:

as built

S. S. Peebles now Gulebra

Mdb report N^o 10380



¹⁴/_M "RENATA"



© 2020

Lloyd's Register
Foundation

008409-008416-0080