

[12 NOV 1947

by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

SOBIESKI  
 ELS NAME ..... REPORT ..... Gdy. 1938  
 No. ....

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

"The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—*Extract from Sub-Committee's Report, 24/5/32.*

The NOTATION of "Examined 5.46", valid for 12 months, is DEFERRED for machinery.

For conditions of class see previous endorsement.

The GDYNIA Surveyor reports (4.47) ship examined on floating dock, bottom coated, the greater part of the requirements of the PERIODICAL SPECIAL SURVEY (C) complied with, and on account of wear and tear a few minor repairs effected.

TO COMPLETE THE S.S.: - see Report.

On account of damage, cause not stated, temporary repairs previously effected in way of shell plate L.5 (s.s) now further temporarily repaired (cement). 4 floors in No. 4 D.B. tank (s.s) reinforced and a number of started rivets in Nos. 7 & 8 D.B. tanks renewed.

4 small fractures in rudder plate (s.s) repaired (E.W.), and recommendation made for same to be examined at the next dry docking.

Permanent repairs effected to shell seam rivets (leaky) in way of forward wing deep tank (p.s), as above.

The indented keel, bottom, and side shell plating, as above, specially examined and found efficient.

In view of the items examined for Special Survey the Surveyor recommends the notation of "Examined 4.47", valid for 12 months, be assigned.

It is submitted the ship is worthy to remain as classed, with record of docking 4.47, subject to permanent repairs to indented keel, bottom, and side shell plating etc. (p & s) and to stern plating etc. (s.s) at the first convenient opportunity and to the rudder plate (s.s) being specially examined at the next dry docking, but without other condition; and to have notation of "Examined 4.47", valid for 12 months, assigned as recommended, and notation of 'S.S. Gdy. - 4.47' WHEN the Survey has been completed.

.47 Gdy. subject  
 without  
 Examined 4.47"

S.S. GREATER PART HELD.



© 2020  
 Lloyd's Register  
 Foundation