

William Gray &amp; Co.Ltd., West Hartlepool.

Yard No.1176.

Similar to the "EMPIRE MAURITIUS", "EMPIRE RABAU", "EMPIRE TAKORALI",  
"EMPIRE NAIROBI" & "PACHUMBA".**F.E.**  
(FBD.)

Received by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

VESSEL'S NAME ..... s.s. "EMPIRE EDDYSTONE" ..... REPORT ..... Hpl. .... No.18670 .....

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

D to W dk 38' (flat sheer). D to 2nd dk 27.25' (flat sheer). D for scantlings 37'  
1st Long. No. 15725 Depth "d" 21.832nd Long. No. 39525 Proportions =  $\frac{L}{D}$  11.18

Framing As approved Sheerstrake As approved

The scantlings of this prefabricated "C" Type Standard Ship have been approved for a draught of 30" in excess of that corresponding to the freeboard which could be assigned as a C.S.S. vessel having a tonnage opening.

The tank top plating has been increased in thickness under the hatchways in lieu of ceiling.

This vessel appears to have been built in accordance with the Rules and the approved plans, and it is submitted she is eligible to be classed **100A1 "With freeboard"**.  
7.45 Hpl.

The Summer Freeboard as shown on the attached extract from the Freeboard Verification Form, now marked on the vessel's sides, to be inserted in the classification certificate and recorded in the Register Book, and further, the remaining freeboards, as shown on the accompanying extract, to be inserted in the certificate of classification.

2 Dks "Butts of keel plating elec.welded" "Longitudinal framing at decks"  
Cell DB 317' 1270t, tank in way of tunnel 323t, wing tanks in mchy space 324t, fwd 282t, FPT 189t, APT 151t

FK, 7BH, pt. Cem., Lloyd's A &amp; CP

F 38'

O.L. 447.8'

E.S.D.

a

*The class is assigned and maintained upon the understanding that the equipment will be made to accord with the requirements of the Rules when the present state of emergency has passed, and that hatch covers at the 2nd deck on Nos 1 & 6 hatchways and cargo battens will be fitted at the first available opportunity.*

Insert in S.R.L.:- (A bower anchor and 45 fathoms of chain cable to be supplied). Hatch covers at the 2nd deck at Nos.1 & 6 hatchways and cargo battens to be fitted at the first opportunity.

It is submitted the Surveyors be requested to state the width of the 2nd deck stringer plate.

008751-008752-0045

2.8.45

Lloyd's Register  
Foundation