

9 - AUG 1956

Rpt. C. 11 (Contd.)

Index No.

39997

Lloyd's Register of Shipping.

Ship's Name "GENERAL SAN MARTIN"

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1951.

Ullage plug to No.5 centre tank in Bridge 'tween deck space, repositioned outside Bridge space, and opening in Upper Deck in Bridge space efficiently plated over. ✓

Companionway to Bridge 'tween deck space. Opening in Bridge deck inside Bridge accommodation plated over, and gas tight hatchway fitted thereto. Hatch opening 27" x 24" with 6" x 3/8" coaming and 3/8" gas tight cover with 4 toggles, manipulated from both sides. ✓

T. B. Tilly
(T. B. TILLEY).

SURVEYOR TO LLOYD'S REGISTER.

LIVERPOOL.

26.6.56.

Copy placed on board ship

16/8/56

