

LLOYD'S REGISTER OF SHIPPING

SHIP OR ENGINE FORGINGS OR CASTINGS

I have to report that the Forgings or ~~Castings~~ as herein described, manufactured
 by **ASSRS. S.I.A.C.** of **GENOA CAMPI**
 Engines No. **A.686 FIAT** being constructed by
 for the Ship No. being built by
M/S "ITALSOLE"
 of
 been inspected by me as set forth below, and found to be, so far as can be seen,
 and free from defects. These have been despatched to ~~MUSEW~~ be fitted
 board the above Vessel.

ITEM	2 JOURNALS	1 JOURNAL	1 SCAVENGE AIR PUMP CRANK
entification No.	LLOYD'S GEN. SS.4646	LLOYD'S GEN. SS.4753	
urveyor's Initials.	G.M.	G.M.	
aterials.	ELECTRIC FURNACE STEEL		
ow made.	FORGED		
eat treated.	NORMALISED		
imensions.	TO SKETCH		
eight.	=		
rogress on Insp.	ROUGH FORGED ROUGH MACHINED & FINISHED		
ield Kgs. per sq. mm.	TL 35.6	BL 35.6	TL 35.6 BL 34.5
lt. Kgs. per sq. mm.	56.1	57.2	57.2 54.3
long. % on 4 d	32.5	28.4	30.0 31.6
educ. of Area %	52.8	51.0	53.7 51.0
old Bend.	180°	GOOD	180° GOOD
rinell.	=		=
zod.	=		=
inal date.	G.M. 19/2/59		

Date of approval of chemical analysis, physical properties and heat treatment in the case of special steels for reduction gearing forgings.

Tests : =

: =

ences :

*Delete where not applicable.

Signature

(G. MAGGI)

Date 23/2/59

© 2021

Lloyd's Register
Foundation

Received at

Office on

Report on Machinery No.

04037

Port

Genoa



© 2021

Lloyd's Register
Foundation