

FREEBOARD VERIFICATION FORM FOR STEAMERS CARRYING TIMBER DECK CARGOES.

Port New Orleans, La. 34231
 Name S.S. "Vestvangen" 2420
LDAX
 Official No. -- No. in Reg. Book 35998
 Port of Registry (For Foreign Ships) Oslo
 Iron or Steel Steel State whether Classed by Lloyd's Register Yes
 Name of Owners Skibs A/S Karaibien Date of Verification 6th November, 1937

I have to report that the Freeboards as given below, assigned by the Committee to this ship, have been correctly marked on the ship's sides, in accordance with the printed instructions:—

ORDINARY CARGO ☒ AND ☐ PASSENGER SHIPS.

Freeboard amidships from top of deck line, wood/steel deck.

						From centre of disc.
Tropical Fresh Water	584	1	ft.	11	ins.	235 1/2 9 1/2 ins. above
Fresh Water	698	2	ft.	3 1/2	ins.	121 4 1/2 ins. above
Tropical	705	2	ft.	3 1/2	ins.	114 4 1/2 ins. above
Summer	819	2	ft.	8 1/2	ins.	
Winter	933	3	ft.	0 1/2	ins.	114 4 1/2 ins. below
Winter North Atlantic	984	3	ft.	2 1/2	ins.	165 6 1/2 ins. below

Fresh water allowance = 12 1/4" = 11 3/4"

SHIPS CARRYING TIMBER DECK CARGOES.

Freeboard amidships from top of deck line, wood/steel deck.

						From centre of disc.
Tropical Fresh Water Timber	0	ft.	11	ins.		21 1/2 ins. above
Fresh Water Timber	1	ft.	3 1/2	ins.		16 1/2 ins. above
Tropical Timber	1	ft.	4	ins.		16 1/2 ins. above
Summer Timber	1	ft.	8 1/2	ins.		11 1/2 ins. above
Winter Timber	2	ft.	3	ins.		5 1/2 ins. { above
Winter North Atlantic Timber	3	ft.	2 1/2	ins.		6 1/2 ins. below

Maximum Summer Draught corresponding to the freeboard assigned as shown on the Builders' Displacement Scales:—

Fresh water allowance = 12 7/8" = 5"

C.W. Murray Surveyor.

(To be filled up in London Office.)

Statement No. 34231 Date of Committee's Minute 15-11-32

Particulars for Record in Register Book. { Moulded Depth 20 ft. 6 ins.
 Freeboard 2 ft. 8 1/4 ins.
 Corresponding Draught 14 ft. 11 1/2 ins.

Freeboards compared and found correct by S.W.B. Date 29/11/37

Is fee paid? Yes Form for Certificate Norwegian

Instructions 289 NOV 1937 Date 30.11.42

Certificate written 1.12.37 Noted for posting Posted