

"TEMPLE YARD"

It is submitted the following cablegram be sent to the New York Office :-

"83460 SUMMER FREEBOARD STEEL SHELTER DECK 10' 8 $\frac{1}{4}$ " ALLOWANCES TROPICAL FRESH 13 $\frac{1}{2}$ FRESH 7 TROPICAL WINTER 6 $\frac{1}{2}$ SUBJECT TONNAGE OPENING FREEING PORTS TONNAGE WELL ALL OVERBOARD SCUPEERS FROM SHELTER TWEEN DECKS PERMANENTLY CLOSED ANY SANITARY DISCHARGES FROM TWEEN DECK SPACES FITTED SCREW-DOWN NON-RETURN VALVES CONTROLLED SHELTER DECK LIFELINES PROVIDED STIFFENING EXPOSED MACHINERY CASINGS RE-INFORCED YOUR SATISFACTION OPENINGS TWEEN DECK BULKHEADS CLOSED ACCORDANCE LATEST INSTRUCTIONS ^{all} TWEEN DECK SPACES DRAINED BILGES STOP HAVE CONSULTED OWNERS WHO AGREE"

A copy of the cablegram should be sent to the Owners.

SZB.

2nd December 1942.



© 2021

Lloyd's Register
Foundation

008917-008924-0121

Pooled.