

Extracts from Lisbon Rpt 8. No. 2622. 1/7/36.

No 3 tank p + s. previously fitted with ordinary cargo hatch coamings and ventilators now modified for carrying oil in bulk as follows. -

Hatches modified as per approved sketch 17/3/38. The ventilator coamings removed and riveted spigot flanges fitted. Air pipes p + s. led up Samson posts now fitted. The suction pipes and valves tested by water pressure in place and found tight.

The main O.T. hatch covers of the No 1 and 2 oil tanks have now also been modified as per approved sketch in lieu of bolted joint originally fitted.

Noted T.W.B.
4/8/36.