

# COPY.

ADV/GIN

S.S. "SAN PIETRO".

Extract from Rotterdam report N°16520, dated 13.6.27.

Survey of condition and repairs. Vessel has been placed in drydock, bottom and rudder cleaned, found or made in good condition and recoated.

Loose rivets in bilge keel renewed. One length bilge keel removed, faired and replaced.

Butts of bottom plating on p.s. in way of B strake, plate N°11; C strake plates Nos. 7 and 10 recaulked and rivets recaulked and edge of butts electrically welded.

On sternframe in way of garboard strake a number of rivets renewed and edges recaulked and also some rivets recaulked on local places. Forward in way of keel plates Nos. 1 and 2 rivets and edges recaulked. Bower anchor.

Transported to shop and a new pin made. Above second arm from bottom on mainpiece some corrosion found, same has been chipped, carefully examined and welded by the Quasi Arc system.

The indented plates on starboard side and other items mentioned in the Special Reasons List not dealt with this time.

It was found that the shaft was down 7/32".



© 2020

Lloyd's Register  
Foundation

009030-009039-0167