

Copy for Lloyd's Register

Lloyd's Register of Shipping.



Port

PUNTA ARENAS MAGALLANES CHILE

5 th. May. 1944.

This is to Certify that

I, Edward S. Hunter,
the undersigned Surveyor to this Society did at the request of

XXXXXXXXXXXXXXXXXXXX


Mr. W. W. Watson, Lloyds Agent at this port, proceed on board the S.S. "RIO VERDE" of 679 tons, of VALPARAISO, anchored in the Punta Arenas Roads, for the purpose of surveying the Main Boiler, and Found :-

2nd. May. The Boiler thoroughly clean and free from scale, the furnace crowns, shell plates, stays and rivets in good condition. The three furnaces and plates of the combustion chambers, tube plates and tubes, clean and in good condition. The manholes, boiler mountings and boiler coatings in good condition.

3rd. May. A hydraulic test was made in my presence to a pressure of 270 lbs. per square inch. No defects appeared.

5th. May. I examined the Main Boiler under the full working steam pressure of 180 lbs. per square inch, at which the safety valves are set.

I hereby recommend that the record be retained as in the register book.



Edward S. Hunter
passed A.M.I. Mech. E. 1926.

SURVEYER APPOINTED BY LLOYDS AGENT

Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—
The Committees of the Society use their best endeavours to ensure that the functions of the Society are properly performed and it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Members or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."

